


**US Army Corps
of Engineers
Mobile District**

NOVEMBER 2017



CONSTRUCTION PLANS FOR

CADD CODE: M017EV17

**PONCE MARINE UNIT - PIER & BOAT RAMP
REPLACEMENT
PONCE, PUERTO RICO**

BASKERVILLE-DONOVAN, INC.
Innovative Infrastructure Solutions

1201 MONTLIMAR DRIVE, SUITE 650
MOBILE, ALABAMA 36609 (334) 380-0311

PENSACOLA - PANAMA CITY BEACH - TALLAHASSEE - MOBILE - BREVARD COUNTY - TAMPA

**FINAL DESIGN
(UNREVIEWED 100%)
SUBMITTAL**

**DRAWINGS IN THIS FOLIO HAVE BEEN REDUCED
TO ONE HALF THE ORIGINAL SCALE**

[illegible]

I. ACCESS

- ## II. COORDINATION






- ### III. TRAFFIC CONTROL

- #### IV. EROSION CONTROL


- ## V. CONTRACTOR SAFETY PLAN SUBMITTALS

1. PROPOSED ACCESS POINTS, STAGING AREA AND HAUL ROUTES.
2. TEMPORARY MARKINGS TO BE USED, IF ANY.
3. LOCATION AND TYPE OF BARRICADES OR OTHER TRAFFIC CONTROL DEVICES.
4. METHODS BY WHICH THE CONTRACTOR WILL COMMUNICATE WITH THE CONTRACTING OFFICER.

VII. SAFETY AND SECURITY REQUIREMENTS

SITE SYMBOL LEGEND		
DESCRIPTION	EXISTING	NEW
BENCHMARK	 OR 	 OR 
SOIL BORING		
CORAL OUTCROPS		
SPOT ELEVATION	 XXX.XX	 XXX.XX
FLOW ARROW		
REMOVAL		
BUILDING		
WETLAND LIMITS		
TRAFFIC SIGN		
BOLLARD	 BLD	 OR  BLD
RIGID PAVEMENT AND JOINTS		
FLEXIBLE PAVEMENT		
GRAVEL		
CENTERLINE		
MAJOR CONTOURS	 0.00	 0.00
MINOR CONTOURS	 0.00	 0.00
TREE LINE OR WOOD LINE		
FENCE – CHAINLINK	 X	 X
FENCE – WOOD BOARD	 //	 //
ROOF DRAIN	 OR  DS	 DS OR  DS
ROOF DRAIN COLLECTION PIPE	 RDC	 RDC
STORM DRAINAGE MANHOLE OR BOX	 OR  D	 D
STORM DRAINAGE PIPE	 SD	 SD
DRAINAGE SWALE		
RIP-RAP		
MONITORING WELL		

DESCRIPTION	EXISTING	NEW
CLEANOUT		
GAS LINE		
JET FUEL LINE		
JET FUEL MANHOLE		
UNKNOWN UTILITY LINE		
RUNWAY OR TAXIWAY LIGHT		
AIR CONDITIONER PAD		
UNDERGROUND FIBER OPTIC LINE		
FIBER OPTIC MARKER		
UNDERGROUND COMMUNICATION LINE		
COMMUNICATION BOX		
COMMUNICATION ANTENNA		
TELEPHONE PEDESTAL		
UNDERGROUND TELEPHONE LINE		
TELEPHONE MANHOLE		
TELEPHONE POLE		
CABLE TV PEDESTAL		
UNDERGROUND CABLE TV LINE		
ELECTRICAL METER		
ELECTRICAL PULL BOX		
ELECTRICAL ACCESS PANEL		
ELECTRICAL TRANSFORMER PAD		
ELECTRICAL PEDESTAL		
ELECTRICAL ALARM PANEL OR BOX		
POWER POLE OR P.P. W/TRANSFORMER		
LIGHT POLE		
ELECTRICAL MANHOLE		
OVERHEAD ELECTRICAL LINE		
UNDERGROUND ELECTRICAL LINE		
GUY WIRE		
CABLE TV PEDESTAL		
UNDERGROUND CABLE TV LINE		
CONDUIT		
SANITARY SEWER FORCE MAIN		
SANITARY SEWER LINE		
SANITARY SEWER MANHOLE OR BOX		
SANITARY SEWER VENT PIPE		
IRRIGATION CONTROL VALVE		
FIRE FLOW VALVE		
FIRE FLOW LINE		
POST INDICATOR VALVE		
WATER LINE		
WATER METER		
WATER BACK FLOW PREVENTOR		
WATER VALVE AND VALVE BOX		
FIRE HYDRANT		
HOSE BIBB		

[illegible]

 BASKERVILLE-DONOVAN, INC. Innovative Infrastructure Solutions		1000 NORTH MAIN STREET, SUITE 200 BASKERVILLE, MISSISSIPPI 39208 TEL: 662-833-1100 FAX: 662-833-1101 WWW.BASKERVILLE-DONOVAN.COM	
US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA		PROJECT NO.: SOLICITATION NO.: CONTRACT NO.: DRAWN BY: T. HYMAN CHECKED BY: J. JOHNSON D. WYATT T. HYMAN PROJECT NUMBER: M01EY17 FILE NAME: 0303EY17.DWG SIZE: A1	

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

GENERAL NOTES AND SYMBOL LEGEND

SHEET ID


X-003

1. ALL DIMENSIONS ARE IN METERS (m), OTHERWISE AS INDICATED.
2. TOPOGRAPHIC SURVEY WAS PERFORMED IN MAY 2016 BY SURVEY ENGINEER RENAN LOPEZ DE AZUA, JAVIER O. ESCOBALES RLDA SURVEYING & MAPPING, SAN JUAN, PUERTO RICO.
3. THE COMPLETE SURVEY REPORT CAN BE OBTAINED FROM THE CONTRACTING OFFICER'S REPRESENTATIVE. REPORT IS 24 PAGE DOCUMENTATION FOR THE DATUM AND GPS POINTS USED FOR THE SURVEY PROVIDED FOR THE DESIGN OF THIS PROJECT.
4. EXISTING CONDITIONS SHOWN IS BASED ON A COMBINATION OF SURVEY, 2004 ASBUILT DRAWINGS FROM THE U.S. CUSTOMS BOATHOUSE PROJECT, AND SUPERPOSED AERIAL IMAGERY.
4. SEE SHEET X-003 FOR SYMBOL LEGEND AND SHEET X-004 FOR ABBREVIATION LEGEND.
5. THE INITIAL GEOTECHNICAL INVESTIGATION WAS COMMISSIONED BY USACE JACKSONVILLE AND PREFORMED ON 22 AUGUST 2016 FOR US CUSTOMS DOCK AND WAVE ATTENUATOR PROJECT AT PONCE, PUERTO RICO. IN ORDER TO OBTAIN MORE DETAILED GEOTECHNICAL DATA FOR PILING, AN ADDITIONAL GEOTECHNICAL INVESTIGATION WAS COMMISSIONED AND PREFORMED BY MGW GEOTECHNICAL GROUP, PSC ON 17 JULY 2017 FOR PROPOSED US COAST GUARD DOCK AT PONCE, PUERTO RICO.
6. ALL CONTOURS AND ELEVATIONS IN WATER ARE NEGATIVE RELATIVE TO MEAN SEA LEVEL (MSL).
7. PIER ALIGNMENT AND PILE PLACEMENT AS INDICATED TO AVOID CORAL OUTCROPS.

DESIGNATION	NORTHING	EASTING
B-1	216072.313	180189.469
B-2	216128.563	180202.472
CB-PBR16-01	216120.090	180242.015
CB-PBR16-02	216113.074	180240.790
CB-PBR16-03	216105.153	180225.858
CB-PBR16-04	216098.448	180234.388

BENCHMARK DATA TABLE				
DESIGNATION	NORTHING	EASTING	ELEVATION	DESCRIPTION
16093-1	216184.294	180224.564	1.146	EXISTING BENCHMARK
C1012	217058.875	180932.021	7.215	EXISTING BENCHMARK
PH-1 USE	215010.181	180102.222	1.694	EXISTING BENCHMARK
PH-2	215170.369	180386.454	1.741	EXISTING BENCHMARK

CORAL OUTCROP LOCATION DATA TABLE						
DESIGNATION	NORTHING	EASTING	DESCRIPTION			
C-1	216117.204	180239.517	EXISTING	HARD	CORAL	COLONIES
C-2	216108.408	180233.696	EXISTING	HARD	CORAL	COLONIES
C-3	216112.703	180236.135	EXISTING	HARD	CORAL	COLONIES
C-4	216114.864	180235.995	EXISTING	HARD	CORAL	COLONIES
C-5	216107.906	180232.410	EXISTING	HARD	CORAL	COLONIES
C-6	216108.878	180228.614	EXISTING	HARD	CORAL	COLONIES
C-7	216105.735	180228.151	EXISTING	HARD	CORAL	COLONIES
C-8	216106.189	180224.988	EXISTING	HARD	CORAL	COLONIES
C-9	216105.655	180221.702	EXISTING	HARD	CORAL	COLONIES
C-10	216104.192	180220.482	EXISTING	HARD	CORAL	COLONIES
C-11	216106.140	180217.660	EXISTING	HARD	CORAL	COLONIES
C-12	216103.855	180215.239	EXISTING	SOFT	CORAL	COLONIES
C-13	216104.885	180213.723	EXISTING	HARD	CORAL	COLONIES
C-14	216106.305	180214.403	EXISTING	HARD	CORAL	COLONIES
C-15	216106.052	180209.631	EXISTING	HARD	CORAL	COLONIES
C-16	216107.969	180207.608	EXISTING	HARD	CORAL	COLONIES
C-17	216110.447	180204.813	EXISTING	HARD	CORAL	COLONIES
C-18	216111.074	180200.703	EXISTING	HARD	CORAL	COLONIES
C-19	216109.052	180198.685	EXISTING	HARD	CORAL	COLONIES
C-20	216109.685	180194.155	EXISTING	SOFT	CORAL	COLONIES
C-21	216112.551	180190.056	EXISTING	HARD	CORAL	COLONIES
C-22	216113.917	180188.866	EXISTING	SOFT	CORAL	COLONIES
C-23	216115.259	180189.424	EXISTING	HARD	CORAL	COLONIES
C-24	216118.083	180186.874	EXISTING	HARD	CORAL	COLONIES
C-25	216120.300	180182.056	EXISTING	HARD	CORAL	COLONIES
C-26	216104.437	180164.511	EXISTING	SUNKEN	VESSEL/DEBRIS	

[illegible]


DESIGNED BY: T. HYMAN	ISSUE DATE: NOVEMBER 2017
DRAWN BY: J. JOHNSON	SOLICITATION NO.: -
CHECKED BY: J. WYATT	CONTRACT NO.: -
SUBMITTED BY: T. HYMAN	PROJECT NUMBER: M017EV17
FILE NAME: C:\014EV17.DWG	

US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT
SURVEY CONTROL AND SOIL
BORING LOCATION PLAN

SHEET ID
C-101


1. SEE SHEET C-101 FOR SURVEY CONTROL POINTS, BENCHMARKS, AND COORDINATES.
2. SEE SHEET X-003 FOR SYMBOL LEGEND AND SHEET X-004 FOR ABBREVIATION LEGEND.
3. ALL EXISTING DEBRIS AND DEBRIS FROM CONSTRUCTION OPERATIONS SHALL BE DISPOSED OF OFF-SITE AT THE CONTRACTOR'S EXPENSE.
4. ALL RIP-RAP TEMPORARILY REMOVED SHALL BE STOCKPILED ON-SITE IN AN APPROVED LOCATION AND REDISTRIBUTED AS REQUIRED.
5. ALL WORK ADJACENT TO OR ON EXISTING ROADWAYS SHALL COMPLY WITH CURRENT LOCAL TRANSPORTATION STANDARDS FOR TRAFFIC CONTROL AND SAFETY. ALL WORK IN AND ADJACENT TO STREETS OR ROADS SHALL BE COORDINATED WITH CONTRACTING OFFICER'S REPRESENTATIVE. THE CONTRACTOR SHALL PROVIDE THE CONTRACTING OFFICER'S REPRESENTATIVE WITH A ONE-WEEK ADVANCE NOTICE PRIOR TO BEGINNING OF WORK ADJACENT TO ROADWAYS. NO WORK ADJACENT TO OR ON EXISTING ROADS SHALL BE INITIATED WITHOUT PRIOR APPROVAL FROM THE CONTRACTING OFFICER'S REPRESENTATIVE.
6. PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL LOCATE ALL UTILITIES. ANY UTILITY ADJUSTMENTS, EXISTING OR PROPOSED, REQUIRED TO COMPLETE CONSTRUCTION UNDER THIS CONTRACT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THIS ITEM INCLUDES, BUT IS NOT LIMITED TO; THE TEMPORARY RELOCATION OF EXISTING OVERHEAD POWER LINES. ALL WORK IN THE VICINITY OF OVERHEAD POWER LINES SHALL CONFORM TO APPLICABLE (LOCAL) SAFETY REQUIREMENTS. THE CONTRACTOR IS TO REPAIR DAMAGES TO EXISTING UTILITIES THAT ARE TO REMAIN IN SERVICE IMMEDIATELY AT NO ADDITIONAL COSTS OR EXPENSE TO THE GOVERNMENT.
7. THE FINAL LAYOUT AND EXTENT OF THE TEMPORARY COFFERDAM WILL BE A FUNCTION OF THE EQUIPMENT OPERATING AREAS AND THE METHOD OF COFFERDAM LATERAL BRACING. THE CONTRACTOR SHALL PROVIDE AN ENGINEERED COFFERDAM INSTALLATION SUFFICIENT TO CONSTRUCT THE PROPOSED BOAT RAMP WITH RIGID PAVEMENT CONSTRUCTION.
8. REMOVE EXISTING RIGID PAVEMENT BOAT RAMP, RIGID PAVEMENT PIER, EXISTING RIP-RAP AND MISCELLANEOUS DEBRIS AS REQ'D. FOR NEW CONSTRUCTION.



SHEET ID
C-102

1. SEE SHEET C-101 FOR SURVEY CONTROL POINTS, BENCHMARKS, AND COORDINATES.
2. SEE SHEET X-003 FOR SYMBOL LEGEND AND SHEET X-004 FOR ABBREVIATION LEGEND.

☐ DENOTES GEOMETRIC POINT
☒ (SEE SHEET C-107
 GEOMETRIC POINT DATA TABLE)

US Army Corps
of Engineers®

Sl. No.	Particulars	Amount	Total
1	...	...	...
2	...	...	...
3	...	...	...
4	...	...	...
5	...	...	...
6	...	...	...
7	...	...	...
8	...	...	...
9	...	...	...
10	...	...	...
11	...	...	...
12	...	...	...
13	...	...	...
14	...	...	...
15	...	...	...
16	...	...	...
17	...	...	...
18	...	...	...
19	...	...	...
20	...	...	...
21	...	...	...
22	...	...	...
23	...	...	...
24	...	...	...
25	...	...	...
26	...	...	...
27	...	...	...
28	...	...	...
29	...	...	...
30	...	...	...
31	...	...	...
32	...	...	...
33	...	...	...
34	...	...	...
35	...	...	...
36	...	...	...
37	...	...	...
38	...	...	...
39	...	...	...
40	...	...	...
41	...	...	...
42	...	...	...
43	...	...	...
44	...	...	...
45	...	...	...
46	...	...	...
47	...	...	...
48	...	...	...
49	...	...	...
50	...	...	...
51	...	...	...
52	...	...	...
53	...	...	...
54	...	...	...
55	...	...	...
56	...	...	...
57	...	...	...
58	...	...	...
59	...	...	...
60	...	...	...
61	...	...	...
62	...	...	...
63	...	...	...
64	...	...	...
65	...	...	...
66	...	...	...
67	...	...	...
68	...	...	...
69	...	...	...
70	...	...	...
71	...	...	...
72	...	...	...
73	...	...	...
74	...	...	...
75	...	...	...
76	...	...	...
77	...	...	...
78	...	...	...
79	...	...	...
80	...	...	...
81	...	...	...
82	...	...	...
83	...	...	...
84	...	...	...
85	...	...	...
86	...	...	...
87	...	...	...
88	...	...	...
89	...	...	...
90	...	...	...
91	...	...	...
92	...	...	...
93	...	...	...
94	...	...	...
95	...	...	...
96	...	...	...
97	...	...	...
98	...	...	...
99	...	...	...
100	...	...	...

ISSUE DATE:	NOVEMBER 2017
DESIGNED BY:	T. HYMAN
DRAWN BY:	J. JOHNSON
CHECKED BY:	D. WYATT
SUBMITTED BY:	T. HYMAN
SOLICITATION NO.:	
CONTRACT NO.:	
PROJECT NUMBER:	MC17EV17
FILE NAME:	

US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE ALABAMA

MOBILE ALABAMA

HOSBIE, ALAN


BASKERVILLE-DONOVAN, INC.
Innovative Infrastructure Solutions
1201 MONTAUNAR DRIVE, SUITE 050, MOBILE AL 36609 (251) 780-0311

ENGINEERING BUSINESS EB-0000340

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT
PIER GEOMETRY AND
MOORING CLEAT
PLACEMENT PLAN



SHEET ID

C-104



1. SEE SHEET C-101 FOR SURVEY CONTROL POINTS, BENCHMARKS, AND COORDINATES.
2. SEE SHEET X-003 FOR SYMBOL LEGEND AND SHEET X-004 FOR ABBREVIATION LEGEND.
3. ELEVATIONS FOR TOP OF ALL RIGID PAVEMENT PADS FOR LIGHTING STRUCTURES TO BE 2.600.

HIGH WATER LEVEL = 0.75
MEAN WATER LEVEL = 0.00±
LOW WATER LEVEL = -0.75

[illegible]

US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA	PROPOSED BY: T. HYMAN	SOLICITATION NO.: NOVEMBER 2017
	DRAWN BY: T. HYMAN	CONTRACT NO.: -
PROJECT NAME: BAKERVILLE PONOVAN, INC. Innovative Infrastructure Solutions	SUBMITTED BY: T. HYMAN	PROJECT NUMBER: MO17EV17
ANSI D	FILE NAME: C10BEV17.DWG	


1201 MONTGOMERY AVENUE, SUITE 1000, MOBILE, AL 36688-2921 (360-231-
 1100)

Purchaser : Panama City Beach - Tallapoosa - Baldwin County - Tampa

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

PIER GRADING PLAN


SHEET ID
C-108



A TYPICAL BOAT RAMP SECTION
C-106 N.T.S.

BOAT RAMP SECTION LEGEND:

- ① EXISTING BOTTOM PROFILE, UNDERCUT TO BE FIELD DETERMINED BASED ON ON-SITE GEOTECHNICAL RECOMMENDATIONS
- ② 152mm GRADED CRUSHED AGGREGATE BASE COURSE, COMPACT TO 95% OF MAXIMUM DRY DENSITY PER ASTM D-1557, MINIMUM CBR 80%
- ③ COMPACTED SUBGRADE, COMPACT TO 95% OF MAXIMUM DRY DENSITY PER ASTM D-1557
- ④ GEOTEXTILE SEPARATION FABRIC
SEE SPECIFICATION 31 00 00 EARTHWORK
- ⑤ STONE RUBBLE BACKFILL (RIP-RAP),
SEE SPECIFICATION 31 00 00 EARTHWORK
- ⑥ 180mm REINFORCED RIGID PAVEMENT RAMP SLAB, GROOVED



TYPICAL PCC RIGID PAVEMENT
BOAT RAMP SECTION
N.T.S.

TYPICAL PAVEMENT SECTION NOTES:


1. PAVEMENT THICKNESS 180mm
2. BASE COURSE THICKNESS 152mm, COMPACT TO 95% OF MAXIMUM DRY DENSITY PER ASTM D-1557, MINIMUM CBR 80%
3. SUBGRADE, COMPACT TO 95% OF MAXIMUM DRY DENSITY PER ASTM D-1557

[illegible]

US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA	ED BASKERVILLE-DONOVAN, INC. Innovative Infrastructure Solutions 1201 MONTAUN DRIVE, SUITE 500, MOBILE, AL 36688-0211 TEL: 251-938-1100 FAX: 251-938-1101 WWW.BASKERVILLE-DOV.COM	T. HYMAN NOVEMBER 2017 SOLICITATION NO.: J. JOHNSON - CHECKED BY: D. WYATT - SUBMITTED BY: T. HYMAN MO17EV47 - PROJECT NUMBER MO17EV47 - CONTRACT NO.: - FILE NAME: C330EV17.DWG ANSI D

BOAT RAMP TYPICAL
PAVEMENT SECTION

SHEET ID
C-300



☑ PROFILE OF BOAT RAMP

- NOTES:
- SEE SHEET C-101 FOR SURVEY CONTROL POINTS, BENCHMARKS, AND COORDINATES.
  - SEE SHEET X-003 FOR SYMBOL LEGEND AND SHEET X-004 FOR ABBREVIATION LEGEND.



MARK	DESCRIPTION	DATE

DESIGNED BY: T. HYMAN	ISSUE DATE: NOVEMBER 2017
DRAWN BY: J. JOHNSON	SOLICITATION NO.:
CHECKED BY: D. WYATT	CONTRACT NO.:
SUBMITTED BY: T. HYMAN	PROJECT NUMBER: NOTED 17
SIZE: ANSI D	FILE NAME: C301EV17.DWG




US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA

BASKERVILLE, DONOVAN, INC.
1201 MONTGOMERY DRIVE, SUITE 600, MOBILE, AL 36688-2511
PROFESSIONAL ENGINEER LICENSE # 15002
Professional Engineer Seal - Civil Engineer - State of Alabama - License # 15002

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

☑ PROFILE OF
BOAT RAMP

SHEET ID
C-301





* JOINT WIDTH SHALL BE AS INDICATED OR AS PER MANUFACTURER'S RECOMMENDATION FOR SPECIFIED JOINT WIDTHS.

- A. NONABSORPTIVE MATERIAL REQUIRED TO PREVENT JOINT SEALANT FROM FLOWING INTO SAWCUT AND TO SEPARATE NONCOMPATIBLE MATERIALS.
- B. PREFORMED FILLER MAY BE FIBERBOARD OR OTHER APPROVED MATERIAL WHICH CAN BE SAWED OR SECTION REMOVED TO FORM SEALANT RESERVOIR.
- C. TOP OF SEALANT SHALL BE AT LEAST 6.350mm BELOW TOP OF PAVEMENT, BUT NO DEEPER THAN 9.525mm.
- D. DIAMETER OF BACKER MATERIAL = $X + 3.175\text{mm}$
- E. SILICONE JOINT SEALANT SHALL BE USED FOR SEALING JOINTS. SEE SPECIFICATION 32 01 19.


JOINTS LOCATED BETWEEN NEW AND EXISTING PAVEMENTS SHALL BE THOROUGHLY CLEANED AND PREPPED PRIOR TO REPLACEMENT OF JOINT SEALANT MATERIAL IN CONFORMANCE WITH THE TECHNICAL SPECIFICATIONS.

THE SURFACE SHALL BE RESPRAYED WITH CURING COMPOUND AS SOON AS FREE WATER DISAPPEARS. NECESSARY PRECAUTIONS SHALL BE TAKEN TO INSURE THAT THE CONCRETE IS PROPERLY PROTECTED FROM DAMAGE AND CURED AT SAWED JOINTS. THE TOP OF THE JOINT OPENING AND THE JOINT GROOVE AT EXPOSED EDGES SHALL BE TIGHTLY SEALED WITH CORD BACKER ROD BEFORE THE CONCRETE IN THE REGION OF THE JOINT IS RESPRAYED WITH CURING COMPOUND, AND SHALL BE MAINTAINED UNTIL REMOVED IMMEDIATELY BEFORE SAWING THE JOINT SEALANT RESERVOIR.




1. REINFORCED PAVEMENT THICKNESS 180mm.
2. STEEL SHALL BE 60 KSI
3. ALL LAPS OF REBAR SHALL BE A MINIMUM 25 BAR DIAMETERS IN LENGTH TIE ALL LAPS.


TYPICAL REINFORCED SLAB DETAIL
N.T.S.




CUT HOLE IN BOTTOM OF STEEL UTILITY TRENCH AT THE ANTICIPATED LOWEST ELEVATION. HOLE DIAMETER TO ACCOMMODATE FLANGED FITTING AND 50mm PVC PIPE.




UTILITY TRENCH AT BOAT RAMP
N.T.S.



UTILITY TRENCH WITH STEEL FRAME AND COVER – PLAN VIEW




C SECTION
C-503 N.T.S.



D SECTION
C-503 N.T.S.

UTILITY TRENCH WITH STEEL FRAME AND COVER
ZURN MODEL NO. Z874-U-9-HD - BASIS OF DESIGN
N.T.S.

UTILITY TRENCH TO BE INSTALLED PER MANUFACTURES REQUIREMENTS. THIS INCLUDES STEEL MITER CUTS OF TRENCH AND DUCTILE IRON COVERS AT GRADE CHANGES AND WELDING OF TRENCH SECTION TO FORM A SOLID TRENCH PRIOR TO CONCRETE PLACEMENT.

[illegible]

DESIGNED BY: T. HYMAN	ISSUE DATE: NOVEMBER 2017
DRAWN BY: J. JOHNSON	SOLICITATION NO.: -
CHECKED BY: D. WYATT	CONTRACT NO.: -
SUBMITTED BY: T. HYMAN	PROJECT NUMBER: M017EV17
FILE NAME: C:\03\EV17.DWG	


US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

UTILITY TRENCH DETAILS

SHEET ID

C-503



A vertical scale with labels A, B, C, D, E, F, and G from bottom to top, with horizontal tick marks.

- 3

2

- D

1


- 2




A

SLOTTED STABLE DETAIL FOR


CATE POST




ROUND POST
N.T.S.




LINE POST
ATTACHMENTS
N.T.S.



END OR GATE POST
N.T.S.




TOP
N.T.S.




ND FOR WIRE STRETCHING
N.T.S.


FASTENING DETAILS—FOR TUBULAR POST OR H—COLUMNS
N.T.S.




LATCH ASSEMBLY
N.T.S.




POST HINGE
N.T.S.



GATE KEEPER
N.T.S.



GATE FRAME HINGE
N.T.S.



DROP BAR ASSEMBLY
N.T.S.




[illegible]

DRAWN BY: J. JOHNSON		SOLICITATION NO.: -	
CHECKED BY:		CONTRACT NO.:	
D. WYATT		PROJECT NUMBER: M07EV17	
SUBMITTED BY:		FILE NAME:	
SIZE:		ANSI D	C65E0V17.DWG

MISCELLANEOUS FENCING DETAILS


1. SEE SHEET C-101 FOR SURVEY CONTROL POINTS, BENCHMARKS, AND COORDINATES.
2. SEE SHEET X-003 FOR SYMBOL LEGEND / SHEET X-004 FOR ABBREVIATION LEGEND.
3. SEE ADDITIONAL NOTES SHEET H-101.

WJB DENOTES WATER LINE JUNCTION BOX WITH CAST IRON LID
(SEE DETAILS ON STRUCTURAL SHEETS AND SHEET H-501)


[illegible][illegible]

PIER WATER OVERVIEW

SHEET ID
H-102



WATER LINE JUNCTION BOX LID DETAIL
N.T.S.



1.00 APPLICABLE CODES

1.01 ALL CONSTRUCTION SHALL CONFORM TO THE LATEST REVISION OF THE INTERNATIONAL BUILDING CODE (IBC 2015).

2.00 TECHNICAL SPECIFICATIONS

THESE GENERAL STRUCTURAL NOTES ARE SUMMARY IN NATURE, THE TECHNICAL SPECIFICATIONS SHALL TAKE PRECEDENCE IN THE CASE OF CONFLICT. THE FOLLOWING TECHNICAL SPECIFICATIONS SHALL GOVERN STRUCTURAL CONSTRUCTION; AND MAY BE SUPPLEMENTED BY OTHERS;

DIV. 3 03 31 29 MARINE CONCRETE

03 45 33 PRECAST PRESTRESSED CONCRETE

DIV. 31 31 62 21 HOLLOW CYLINDRICAL STEEL PIPE PILES CONCRETE FILLED

3.00 COORDINATION GENERAL NOTES

3.01 THE DESIGN, ADEQUACY, AND SAFETY OF ERECTION BRACING, TEMPORARY SUPPORTS, AND CONTROL OF ABOVE AND BELOW GROUND SURFACE WATER CONTROL, IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

3.02 COORDINATE STRUCTURAL CONTRACT DOCUMENTS WITH ELECTRICAL, PLUMBING, COMMUNICATIONS AND CIVIL. CONTRACTOR SHALL MAKE NO DEVIATION FROM DESIGN DRAWINGS WITHOUT WRITTEN APPROVAL OF THE CONTRACTING OFFICER'S REPRESENTATIVE.

3.03 THE CONTRACTOR REMAINS SOLELY RESPONSIBLE FOR SHOP DRAWING COORDINATION.

3.04 THE CONTRACTOR IS RESPONSIBLE FOR MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES OF CONSTRUCTION.

3.05 DO NOT PLACE PIPES OR DUCTS EXCEEDING ONE-THIRD THE SLAB OR WALL THICKNESS WITHIN STRUCTURES UNLESS SPECIFICALLY SHOWN AND DETAILED ON STRUCTURAL DRAWINGS.


4.00 FOUNDATION DESIGN CRITERIA/DATA

4.01 A GEOTECHNICAL INVESTIGATION REPORT HAS BEEN PERFORMED BY MGV GEOTECHNICAL GROUP, PSC. JOB NO. 1697, DATED JULY 17, 2017.

5.00 MINIMUM MATERIAL DESIGN STRENGTHS

5.01 CONCRETE -28 DAY COMPRESSIVE STRENGTH = 5000 psi = 35 MPa

5.02 STEEL REINFORCING $-f_y$ = 60,000 psi = 414 MPa

[illegible]



US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA	 BASKERVILLE DONOVAN, INC. INNOVATIVE INFRASTRUCTURE SOLUTIONS 1321 NORTH BAYVIEW BLVD, SUITE 100 MOBILE, AL 36688-2131 (364) 671-1100 www.baskervilledonovan.com	D. HYMAN D. HYMAN D. HYMAN D. WYATT	NOVEMBER 2017 SOLICITATION NO.: CONTRACT NO.: PROJECT NUMBER: MOT/ET/17
		SUBMITTED BY: T. HYMAN T. HYMAN T. HYMAN D. WYATT	FILE NAME: XXXXXDLWG

Particulars - Planning City: Beach - Tallahassee - Mobile - Broward County - Tampa

PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

GENERAL STRUCTURAL NOTES

SHEET ID
S-001



KEYNOTES		(X-X.XX)
2-3.30	STEEL PIPE PILE w/ DRIVING SHOE, CONCRETE FILLED, SEE SCHEDULE	
3-1.01	PILE CAP, SEE SCHEDULE	
3-10.0 1	PRECAST CONCRETE BEAM, SEE SCHEDULE	

LEGEND

BMx FRAMING MEMBER; SEE SCHEDULE SHEET S-120

PILE CAP x PILE CAP; SEE SCHEDULE SHEET S-121

Pxxx PILE MARK, SEE SCHEDULE SHEET S-121

B-x  SOIL BORING LOCATION (GEOTECHNICAL REPORT PROVIDED BY MGV GEOTECHNICAL GROUP, PSC, DATED JULY 17, 2017)

US Army Corps
of Engineers®[illegible]




US ARMY CORPS OF ENGINEERS	BASKERVILLE-DONOVAN, INC.
MOBILE DISTRICT	Innovative Infrastructure Solutions
MOBILE, ALABAMA	ENGINEERING • DESIGN • CONSTRUCTION
	1201 S. MARTIN LUTHER KING, JR. BLVD., SUITE 200 (917) 680-0111
	HOUSTON • MEMPHIS • MIAMI • MOBILE • NEW ORLEANS • TAMPA
	PORTLAND • PHOENIX CITY BRANCH • RICHMOND • MOBILE • BIRMINGHAM • TALLAHASSEE

PONCE, PUERTO RICO
 PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT
 FIXED PIER, PILE CAP AND
 BEAM LAYOUT PLANS

FIXED PIER, PILE CAP AND BEAM LAYOUT PLANS

SHEET ID

S-100



PRECAST BEAM SCHEDULE			
MARK	DESIGNATION	DESCRIPTION	COMMENTS
BM1	26LB36	PRECAST L-BEAM	NOMINAL SIZE SHOWN. FINAL SIZE BY DELEGATED ENGINEER
BM2	20LB24	PRECAST L-BEAM	NOMINAL SIZE SHOWN. FINAL SIZE BY DELEGATED ENGINEER

- LEGEND**
- Sx SLAB; SEE SCHEDULE SHEET S-121
  - BMx FRAMING MEMBER; SEE SCHEDULE SHEET S-120
  - PILE CAP x PILE CAP; SEE SCHEDULE SHEET S-121

KEYNOTES	
MARK	DESCRIPTION
2-3.30	STEEL PIPE PILE w/ DRIVING SHOE, CONCRETE FILLED, SEE SCHEDULE
3-1.01	PILE CAP, SEE SCHEDULE
3-10.01	PRECAST CONCRETE BEAM, SEE SCHEDULE
1	150 mm PRECAST SOLID FLAT SLAB
2	15 mm PRE-FORMED EXPANSION JOINT MATERIAL - RECESS 30 mm + PLACE JOINT SEALANT
3	2" PVC CONDUIT SLEEVE WITH FITTINGS & STAINLESS STEEL ROUTING CLAMPS FOR WATER LINE
4	1" PVC ELECTRICAL CONDUIT SLEEVE WITH FITTING & STAINLESS STEEL ROUTING CLAMPS
5	20 mm CHAMFER ALL CONCRETE EXPOSED EDGES.
6	CONCRETE BONDING ADHESIVE
7	CAST IRON LID SEE SHEET H-501 FOR DETAILS




US Army Corps of Engineers

ISSUE DATE: NOVEMBER 2017	SOLICITATION NO.:	CONTRACT NO.:	PROJECT NUMBER: MOT7EV17	FILE NAME: S120EV17.DWG	DATE
DESIGNED BY: T. HYMAN	DRAWN BY: J. JOHNSON	CHECKED BY: D. WYATT	SUBMITTED BY: T. HYMAN	SIZE: ANSI D	MARK
US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA BASKERVILLE-DONOVAN, INC. Innovative Infrastructure Solutions 190 MONTAGNE DRIVE, SUITE 200, MOBILE, AL 36688-1111 Phone: 251-938-1111 Fax: 251-938-1112 www.baskervilledonovan.com					

FIXED PIER SECTIONS

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

SHEET ID
S-120



GENERAL NOTES

- 1. STEEL PIPE PILES SHIPPED w/(3) COATS COAL TAR EPOXY PROTECTIVE COATING.
- PILE STORAGE AND HANDLING TO PREVENT COATING DAMAGE.
- MINIMUM 3 COATS TOUCH UP FOLLOWING FIELD WELDMENT.

KEYNOTES (X-XXX) (X)	
MARK	DESCRIPTION
2-3.30	STEEL PIPE PILE w/ DRIVING SHOE, CONCRETE FILLED, SEE SCHEDULE
1	STEEL DRIVE SHOE
2	STEEL PIPE PILE SPICER

SLAB REINFORCING SCHEDULE			
DESCRIPTION	MARK	THICKNESS	COMMENTS
SLAB TOPPING (CAST-IN-PLACE)	S1	150 mm	#10M @ 200 mm O.C.E., TOP
SOLID FLAT SLAB (PRECAST)	S2	150 mm	PER MANUFACTURER
SECONDARY POUR (CAST-IN-PLACE)	S3	300 mm	6-#10M CONT. w/ #10M STIRRUPS @ 300 mm O.C.
CONCRETE RAMP (CAST-IN-PLACE)	S4	150 mm	#16M @ 150 mm O.C.E.W, CENTERED

PILE CAP SCHEDULE			
MARK	SIZE	REINFORCING	L2 BARS
PILE CAP 1	1350 mm WIDE x 600 mm DEEP	5-#16M BARS T&B CONT. w/ #16M BARS T&B TRANSVERSE 180° HOOK BOT., 90° HOOK TOP	2-#16M BARS, CONT. BOT. w/ #16M 2-LEG STIRRUPS @ 300 mm O.C.
PILE CAP 2	1350 mm WIDE x 600 mm DEEP	5-#16M BARS T&B CONT. w/ #16M BARS T&B TRANSVERSE 180° HOOK BOT., 90° HOOK TOP	2-#16M BARS, CONT. BOT. w/ #16M 2-LEG STIRRUPS @ 300 mm O.C.
PILE CAP 3	1350 mm WIDE x 600 mm DEEP	5-#16M BARS T&B CONT. w/ #16M BARS T&B TRANSVERSE 180° HOOK BOT., 90° HOOK TOP	2-#16M BARS, CONT. BOT. w/ #16M 2-LEG STIRRUPS @ 300 mm O.C.
PILE CAP 4	1350 mm WIDE x 600 mm DEEP	5-#16M BARS T&B CONT. w/ #16M BARS T&B TRANSVERSE 180° HOOK BOT., 90° HOOK TOP	2-#16M BARS, CONT. BOT. w/ #16M 2-LEG STIRRUPS @ 300 mm O.C.
PILE CAP 5	1350 mm WIDE x 600 mm DEEP	5-#16M BARS T&B CONT. w/ #16M BARS T&B TRANSVERSE 180° HOOK BOT., 90° HOOK TOP	2-#16M BARS, CONT. BOT. w/ #16M 2-LEG STIRRUPS @ 300 mm O.C.
PILE CAP 6	1350 mm WIDE x 600 mm DEEP	5-#16M BARS T&B CONT. w/ #16M BARS T&B TRANSVERSE 180° HOOK BOT., 90° HOOK TOP	2-#16M BARS, CONT. BOT. w/ #16M 2-LEG STIRRUPS @ 300 mm O.C.
PILE CAP 7	1350 mm WIDE x 600 mm DEEP	5-#16M BARS T&B CONT. w/ #16M BARS T&B TRANSVERSE 180° HOOK BOT., 90° HOOK TOP	2-#16M BARS, CONT. BOT. w/ #16M 2-LEG STIRRUPS @ 300 mm O.C.

STEEL PIPE PILE SCHEDULE						
LOCATION	MARK	U/S PILE CAP OR PIER EL.	PILE TOP EL. (CUT-OFF)	TIP EL.	DESIGN AXIAL COMPRESSIVE LOADS (TONS)	DESIGN AXIAL LATERAL LOADS (TONS)
PILE CAP 1	P001-P002	+0.150 M	+0.450 M	-30.350 M	27.6 T	1.0 T
PILE CAP 2	P003-P004	+1.250 M	+1.550 M	-29.250 M	37.3 T	1.0 T
PILE CAP 3	P005-P006	+1.250 M	+1.550 M	-29.250 M	27.3 T	1.0 T
PILE CAP 4	P007-P008	+1.250 M	+1.550 M	-29.250 M	27.3 T	1.0 T
PILE CAP 5	P009-P010	+1.250 M	+1.550 M	-29.250 M	27.3 T	1.0 T
PILE CAP 6	P011-P012	+1.250 M	+1.550 M	-29.250 M	27.3 T	1.0 T
PILE CAP 7	P013-P014	+1.250 M	+1.550 M	-29.250 M	27.3 T	1.0 T
MOORING DOLPHIN PILES	P015-P018	--	+3.500 M	-27.000 M	17.6 T	1.0 T
TENSION PILE	--	--	+3.400 M	-37.100 M	--	1.0 T

- NOTES:
- 1) PROVIDE TWO (2) DYNAMIC TEST PILES AND ONE (1) TENSION PILE INDICATED PER PLAN.
  - 2) FABRICATE, SHIP AND DRIVE A PILE LENGTH 600 mm HIGHER THAN TOP OR CUT-OFF ELEVATION. TRIM IN THE FIELD.
  - 3) PILE COMPRESSIVE CAPACITY LISTED COMPUTED AT NOMINAL BEARING RESISTANCE PER GEOTECH LESS TENSION PILE / SAFETY FACTOR OF 2.00
  - 4) DESIGN AXIAL SERVICE LOADS INCLUDE ALL PILES, PILE CAPS AND PIER WEIGHTS. UNFACTORED LOADS AND LIVE LOADS.
  - 5) ALL PILES SHALL BE FILLED WITH CONCRETE

US Army Corps of Engineers®


ISSUE DATE: NOVEMBER 2017	SOLICITATION NO.:	CONTRACT NO.:	PROJECT NUMBER: MD7EV7	FILE NAME: S21EV7.DWG
DESIGNED BY: T. HYMAN	DRAWN BY: J. JOHNSON	CHECKED BY: D. WYATT	SUBMITTED BY: T. HYMAN	SIZE: A
US ARMY CORPS OF ENGINEERS	MOBILE DISTRICT	MOBILE, ALABAMA	BASKERVILLE-DONOVAN, INC. Innovative Infrastructure Solutions 1901 MONTICLOE DRIVE, SUITE 200, MOBILE, AL 36688-2001 Permitted - Federal City Beach - Indian Rocks - Mobile - Shreve County - Tampa	

POUCE, PUERTO RICO


POUCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

STEEL PIPE PILE DETAILS AND SCHEDULES

SHEET ID
S-121




TYP. CONCRETE DECK CONNECTION PLAN




KEYNOTES		(X-X.XX)	(X)
MARK	DESCRIPTION		
2-3.30	STEEL PIPE PILE w/ DRIVING SHOE, CONCRETE FILLED, SEE SCHEDULE		
3-1.01	PILE CAP, SEE SCHEDULE		
3-3.73	CONCRETE GROUT w/BONDING ADHESIVE (3000 psi)		
3-10.01	PRECAST CONCRETE BEAM, SEE SCHEDULE		
1	150 mm PRECAST SOLID FLAT SLAB		
2	50 mm BUILD UP TFE (TEFLON) BEARING PAD		
3	300 mm x 300 mm x 16 mm THICK 316 STAINLESS STEEL PLATE W/ 2-16 mm HEADED STUDS		
4	25.4mm $\varnothing$ THREADED ROD w/ NUT & WASHER TOP & BOT.		
5	100 mm x 100 mm x 16 mm THICK 316 STAINLESS STEEL FLAT BAR		
6	100 mm x 150 mm x 16 mm THICK 316 STAINLESS STEEL PLATE WITH 2-16 mm $\varnothing$ x 100 mm HEADED STUDS		
7	BUILD UP TFE (TEFLON) BEARING PAD		
8	EPOXY EMBED REINFORCING 125 mm INTO PRECAST BEAM AT 600 mm O.C.		
9	100 mm x 305 mm x 305 mm HOUSEKEEPING PAD w/ 3-#10M HARPINS. FINAL SIZE TO ACCOMMODATE BASE PLATE AND 20 mm CHAMFER		
10	20 mm CHAMFER ALL CONCRETE EXPOSED EDGES.		
11	PVC PIPE SLEEVE AT SECONDARY POUR FOR ELECTRICAL CONDUIT		
12	FASTEN CONDUIT TO PRECAST SLABS w/ STAINLESS STEEL CONDUIT ROUTING CLAMPS		
13	100 mm x 75 mm x 16 mm THICK 316 STAINLESS STEEL FLAT BAR		
14	15 mm PRE-FORMED EXPANSION JOINT MATERIAL - RECESS 30 mm + PLACE JOINT SEALANT		
15	CONCRETE BONDING ADHESIVE		
16	1" PVC ELECTRICAL CONDUIT SLEEVE WITH FITTING & STAINLESS STEEL ROUTING CLAMPS		

LEGEND




- Sx** SLAB; SEE SCHEDULE SHEET S-121
Emx FRAMING MEMBER; SEE SCHEDULE SHEET S-120
PILE CAP x PILE CAP; SEE SCHEDULE SHEET S-121
 E.J. SLAB EXPANSION JOINT





BEAM/SLAB TOPPING CONNECTION DETAIL





TYP. LED BOLLARD MOUNTING DETAIL




BEAM/PILE CAP CONNECTION DETAIL



POWER PEDESTAL DETAIL





UTILITY PILE CAP INTERFACE DETAIL




RAILING LEGEND

- g = GUARDRAIL 1066 mm
 s = SLAB MOUNTED



TYP. GUARDRAIL DETAIL



US Army Corps
of Engineers®

[illegible]

 BASKERVILLE-DONOVAN, INC. INNOVATIVE INFRASTRUCTURE SOLUTIONS 1201 HOLLAND DRIVE, SUITE 1000, ALBUQUERQUE, NM 87102 (505) 262-0211 PROJECTS • POWER CABLE TENSIONING • MODULAR • STRENGTHENING • TANKS	US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA	DESIGNED BY: T. HYMAN	ISSUE DATE: NOVEMBER 2017
		DRAWN BY: J. JOHNSON	SOLICITATION NO.: -
		CHECKED BY: D. WYATT	CONTRACT NO.: -
		SUBMITTED BY: T. HYMAN	PROJECT NUMBER: MOTV1717
		FILE NAME: ANSID_	SYNOPSIS.DWG

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

FIXED PIER DETAILS


SHEET ID

S-122

- D

B

CEILING OUTLET - BOX, FLANGE, SUPPORT, ETC.
WALL OUTLET - BOX, FLANGE, SUPPORT WITH LUMINAIRE OR DEVICE & DEVICE PLATE.
WALL SWITCH - BOX, FLANGE, SUPPORT, DEVICE & DEVICE PLATE.
JUNCTION BOX - BOX, SUPPORT & COVER.
BRANCH CIRCUIT - CONDUIT, CONDUCTORS & CONTINUOUS GROUNDING PATH.
(SEE ASSIGNATION B)S
EQUIPMENT GROUND - CONDUCTOR FOR CONNECTING NONCURRENT-CARRYING METAL
PARTS OF EQUIPMENT, ENCLOSURES, RACEWAYS, ETC.
SIZED IN ACCORDANCE WITH NFPA 70, CURRENT N.E.C.



U S A R M Y C O R P S O F E N G I N E E R S M O B I L E D I S T R I C T M O B I L E , A L A B A M A		DESIGNED BY: DRAWN BY: EWI, TEW: CHECKED BY: KLH PROJECT NUMBER: M07E1V17	ISSUE DATE: NOVEMBER 28/17 SOLICITATION NO.: CONTRACT NO.:
BASKERVILLE-PONOVAN, INC. Innovative Infrastructure Solutions 1201 MONTI LANE, SUITE 400, MOBILE, AL 36688 (904) 580-0211 www.baskerville-inc.com		SUBMITTED BY: KLH	FILE NAME: E00E1V17.dwg
ANSI D		SIZE:	

Plotted by: Plotted: CV Baskin - Technician - Mobile - Baskerville - Texas

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

ELECTRICAL SYMBOL LEGEND & ABBREVIATIONS

SHEET ID:

E-001

SIZE AWG OR KCMIL	AREA	
	mm ² (NOTE 4)	CIRCULAR MILS
18	1.0	1,620
16	1.5	2,580
14	2.5	4,110
12	4	6,530
10	6	10,380
8	10	16,510
6	16	26,240
4	25	41,740
2	35	66,360
1/0	50	105,600
2/0	70	133,100
3/0	95	167,800
4/0	120	211,600
300	150	300,000
350	185	350,000
500	240	500,000
600	300	600,000
750	400	750,000

NOTES

1. UNLESS NOTED OTHERWISE ALL LOW VOLTAGE CONDUCTORS SHALL BE RATED AT 600 VOLTS AND THE INSTALLATION BASED UPON AN AMBIENT TEMPERATURE OF 30°C AS FOLLOWS:
  - METAL – COPPER
  - INSULATION – SEE SPECIFICATIONS
  - TEMPERATURE RATING – 75°C
  - LOCATION – WET OR DRY
2. CONDUCTORS SHALL BE IDENTIFIED BY SURFACE MARKINGS FROM THE MANUFACTURER:
  - MANUFACTURER'S IDENTIFICATION
  - CONDUCTOR SIZE AND METAL
  - VOLTAGE RATING
  - UL LISTING
  - TYPE DESIGNATION & OPTIONAL RATINGS
3. CONDUCTORS SHALL BE LABELED BY THE CONTRACTOR, FOR ANY CIRCUIT 60 AMPERES AND HIGHER, IN EACH PULLBOX, J-BOX OR WIREWAY AS FOLLOWS:
  - PANEL SOURCE & CIRCUIT BREAKER SIZE
  - DESTINATION (LOAD SERVED)
4. THE mm² VALUE INDICATED ARE ACTUAL TRADE SIZES THAT CAN BE PURCHASED AND CONSIDERED EQUAL. THEY ARE NOT THE ACTUAL MEASURED AREA.

		<u>NOTES:</u>
	2-4mm2 & 1-4mm2 GRD - 16mmC	1. LARGER SIZE CONDUCTORS SHALL BE USED WHEN INDICATED AND AS REQUIRED FOR DERATING.
	3-4mm2 & 1#4mm2 GRD - 16mmC	2. ALL CIRCUITS SHALL CONTAIN A GREEN EQUIPMENT GRD CONDUCTOR.
	4-4mm2 & 1-4mm2 GRD - 21mmC	3. EQUIPMENT GROUND CONDUCTOR SHALL BE AS FOLLOWS UNLESS OTHERWISE INDICATED:
	5-4mm2 & 1-4mm2 GRD - 21mmC, ETC.	• 4mm2 CIRCUIT - 4mm2 GRD
	2-6mm2 & 1-6mm2 GRD - 16mmC*	• 6mm2 CIRCUIT - 6mm2 GRD
	3-6mm2 & 1-6mm2 GRD - 21mmC, ETC.	• 10mm2 CIRCUIT - 6mm2 GRD
	2-10mm2 & 1-6mm2 GRD - 21mmC	4. UNLESS OTHERWISE INDICATED, CONDUIT SIZE IS BASED UPON MAX NO. ALLOWED BY NEC UTILIZING A MAX ALLOWABLE PERCENTAGE FILL OF 40%. SEE CHAPTER 9 OF NEC.
	3-10mm2 & 1-6mm2 GRD - 27mmC, ETC.	5. METRIC DESIGNATORS ARE BASED UPON INDUSTRY STANDARDS. SEE CONDUIT AND TUBING SCHEDULE.
	3-16mm2 & 1-6mm2 GRD - 27mmC, ETC.	

	2#12 & 1#12 GRD - 1/2"	NOTES: 1. LARGER SIZE CONDUCTORS SHALL BE USED WHEN INDICATED AND AS REQUIRED FOR DERATING. 2. ALL CIRCUITS SHALL CONTAIN A GREEN EQUIPMENT GRD CONDUCTOR. 3. EQUIPMENT GROUND CONDUCTOR SHALL BE AS FOLLOWS UNLESS OTHERWISE INDICATED: • #12 AWG CIRCUIT - #12 GRD • #10 AWG CIRCUIT - #10 GRD • #8 AWG CIRCUIT - #10 GRD 4. UNLESS OTHERWISE INDICATED, CONDUIT SIZE IS BASED UPON MAX NO. ALLOWED BY NEC UTILIZING A MAX ALLOWABLE PERCENTAGE FILL OF 40%. SEE CHAPTER 9 OF NEC. 5. METRIC DESIGNATORS ARE BASED UPON INDUSTRY STANDARDS. SEE CONDUIT AND TUBING SCHEDULE.
	3#12 & 1#12 GRD - 1/2"	
	4#12 & 1#12 GRD - 3/4"	
	5#12 & 1#12 GRD - 3/4", ETC..	
	2#10 & 1#10 GRD - 1/2"	
	3#10 & 1#10 GRD - 3/4", ETC.	
	2#8 & 1#10 GRD - 3/4"	
	3#8 & 1#10 GRD - 1", ETC.	
	3#6 & 1#10 GRD - 1", ETC.	

TYPICAL FEEDER DESIGNATIONS

The diagram illustrates the components of a typical feeder designation: **# & 1#_GRD - C (_A/_P)**.

- #**: NUMBER OF CIRCUIT CONDUCTORS
- & 1#**: SIZE OF CIRCUIT CONDUCTORS "AWG UNLESS NOTED kCMIL"
- _GRD**: SIZE OF GROUNDING CONDUCTOR
- C**: CONDUIT SIZE
- (_A/_P)**: PROTECTIVE DEVICE TO WHICH THE CIRCUIT IS CONNECTED

NOTES:

1. CONDUCTOR INSULATION TO BE 600V UNLESS OTHERWISE INDICATED.
2. SEE FEEDER SCHEDULE

CONDUIT SIZE		NOTES
METRIC DESIGNATOR (mm)	NEC TRADE SIZE REF NO.	1. THE METRIC DESIGNATORS AND TRADE SIZES ARE FOR IDENTIFICATION PURPOSES ONLY AND NOT EXACT DIMENSIONS. 2. SEE NEC TABLE FOR METRIC DESIGNATOR AND TRADE SIZES. 3. MINIMUM SIZE CONDUIT OR TUBING SYSTEM TO BE USED SHALL BE 16mm. THE 12mm SHALL BE USED ONLY FOR SPECIAL EQUIPMENT CONNECTIONS OR LUMINAIRE WHIPS AS AN ASSEMBLY COMPONENT OR INTEGRAL PARTS OF EQUIPMENT. 4. CONDUIT FILL SHALL BE BASED ON 40% FILL OF CROSS SECTION OF CONDUIT FOR NOMINAL CONDITIONS: • 3 OR MORE CONDUCTORS • LENGTH OF PULLS MINIMIZED • NUMBER OF BENDS LIMITED • ADEQUATE HEAT DISSIPATION OTHERWISE CONDUIT SIZE SHALL BE INCREASED. 5. SEE TYPICAL RACEWAY/CONDUIT INSTALLATION DETAILS.
12	3/8	
16	1/2	
21	3/4	
27	1	
35	1 1/4	
41	1 1/2	
53	2	
63	2 1/2	
78	3	
91	3 1/2	
103	4	
129	5	
155	6	

The diagram illustrates the symbols used for identifying details, sections, and elevations in architectural drawings, and how they are referenced in a typical note.

Detail Identification: A circle with a horizontal line through its center and a dot above the line. Labels indicate:

- DETAIL IDENTIFICATION
- SHEET ON WHICH DETAIL IS DRAWN

Section Identification: A circle with a horizontal line through its center and a triangle above the line. Labels indicate:

- SECTION IDENTIFICATION
- SHEET ON WHICH SECTION IS DRAWN

Elevation Identification: A circle with a horizontal line through its center and a semi-circle above the line. Labels indicate:

- ELEVATION IDENTIFICATION
- SHEET ON WHICH ELEVATION IS DRAWN


TYPICAL NOTE REFERENCE: A diagram showing how these symbols are used in a note. The word "SEE" is followed by a horizontal line. A vertical line with a horizontal tick mark points to the "SHEET ON WHICH DRAWN" part of the symbol. Another vertical line with a horizontal tick mark points to the "DETAIL, SECTION OR ELEVATION IDENTIFICATION" part of the symbol. A third vertical line with a horizontal tick mark points to the "DETAIL, SECTION OR ELEVATION" part of the symbol.

MARK	PURPOSE	NOTES
(A)	DIMENSION REFERENCE	SEE CORRESPONDING DIMENSION BLOCK APPLICABLE LETTER INDICATED
(I)	KEY NOTE REFERENCE	SEE CORRESPONDING KEY NOTE APPLICABLE NUMBER INDICATED
(E)	EQUIPMENT REFERENCE	SEE CORRESPONDING EQUIPMENT SCHEDULE COORDINATE WITH APPLICABLE DIVISIONS
(A)	FEEDER REFERENCE	SEE CORRESPONDING FEEDER SCHEDULE APPLICABLE LETTER INDICATED

 A LUMINAIRE TYPE 'A', CIRCUIT NO. 1, CONTROLLED BY SWITCH "a"
 FT2 **b** LUMINAIRE TYPE 'FT2', CIRCUIT NO. 2, CONTROLLED BY SWITCH "b"
 2 WALL OUTLET WITH RECEPTACLE NOTED, CONNECT TO CIRCUIT NO. 2
 L-1 HOMERUN TO PANEL 'L', CONNECT TO CIRCUIT NO 1
 1 EQUIPMENT CONNECTION - CONNECT TO CIRCUIT NO. 1

Diagram illustrating the connection of a switch assembly (Type Noted) to a common device plate and outlets marked "a" and "b".

- SWITCH ASSEMBLY (TYPE NOTED)
- COMMON DEVICE PLATE
- SWITCH FOR OUTLETS MARK "a"
- SWITCH FOR OUTLETS MARK "b"

[illegible]

US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA	BASKERVILLE-DONOVAN, INC. Innovative Infrastructure Solutions 1201 MONTGOMERY BLVD., SUITE 200 PRICHARD, ALABAMA 36606 PHONE: (205) 666-0200 FAX: (205) 666-0211		K/LH SIGNED BY: _____ DATE: _____
	DRAWN BY: _____ EWH: TEW CHECKED BY: _____	SOLICITATION NO.: _____ CONTRACT NO.: _____	PROJECT NUMBER: _____ FILE NAME: _____ SIZE: _____ ANSD: _____ ECODEV17.dwg

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

GENERAL ELECTRICAL DESIGNATIONS

SHEET ID

E-002

KEYED NOTES

- 1 TYPE EXPANSION/DEFLECTION FITTING LOCATION.
* SEE SHEET NOTE 2

SHEET NOTES

1. CONDUIT FOR PIER LIGHTING AND POWER PEDESTALS ARE TO BE POURED IN CONCRETE. SEE DETAIL B/E-502.
2. INSTALL EXPANSION/DEFLECTION FITTINGS AT ALL PIER EXPANSION JOINTS. COORDINATE WITH SHEET S-101 FOR ALL LOCATIONS.



US Army Corps
of Engineers®


[illegible]


US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA		DESIGNED BY: K/H	ISSUE DATE: NOVEMBER 2017
		DRAWN BY: EWH, TEW	SOLICITATION NO.:
		CHECKED BY:	CONTRACT NO.:
		K/H	
		SUBMITTED BY:	PROJECT NUMBER:
		K/H	MOTV17
		SIZE:	FILE NAME:
		1/8" = 1'	170717.Awt

BASKERVILLE-DONOVAN, INC.
 Innovative infrastructure solutions
 15001 HORTON LAKE DRIVE, SUITE 300, MOBILE, AL 36688 (251) 385-0311
 19500 Highway 90, Suite 100, Gulfport, MS 39503 (601) 833-3333
 Locations • Pearl River City Center • Wilmette • Broward County • Tampa


PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT
**FIXED PIER
ELECTRICAL PLAN**

SHEET ID
E-201





TX: P1
 15 kVA
 PRI: 240V, 1 PH
 SEC: 480V, 1PH
 WALL MTD 7'-0"



SHEET NOTES

- CONDUIT FITTINGS SHALL BE INSTALLED IN THE UTILITY TRENCH AT LOCATIONS FOR 90° TURNS. INSTALL COVERS ACCESSIBLE FOR CABLE PULLING.

KEYED NOTES

- EXIT BUILDING WITH 'LB' AND RUN DOWN EXTERIOR WALL.
* TRENCH/CUT/PATCH/REPAIR
- INSTALL CONDUIT SYSTEMS FROM EXISTING BUILDING AND BACKBOARD-P. TURNS SHALL BE VIA CONDULET FITTINGS WITH GASKETED COVERS ON TOP FOR PULLING CONDUCTOR ACCESS.
* OFF-SET CONDUIT AS REQUIRED
* STAGGER FITTINGS AS REQUIRED
* SEE DETAIL C/E502

US Army Corps of Engineers

DESIGNED BY:		ISSUE DATE:		SHEET ID	
KLH	KLH	NOVEMBER 2017	NOVEMBER 2017	E-202	E-202
DRAWN BY:		SOLICITATION NO.:		MARK	
KLH	KLH	MOBILE DISTRICT	MOBILE DISTRICT	DESCRIPTION	
CHECKED BY:		CONTRACT NO.:		DATE	
KLH	KLH	MOBILE, ALABAMA	MOBILE, ALABAMA		
SUBMITTED BY:		PROJECT NUMBER:			
KLH	KLH	1201 MONTGOMERY DRIVE, SUITE 600, MOBILE, AL 36688-1311	1201 MONTGOMERY DRIVE, SUITE 600, MOBILE, AL 36688-1311		
FILE NAME:		E202EVT7.dwg			
SIZE:		ANSI D			

PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT


LARGE SCALE PLANS

SHEET ID

E-202

DETAIL KEYED NOTES


- ① LOCK-NUT ASSEMBLIES
- ② METAL GROUNDING BUSHING
- ③ COPPER GROUND LUG
- ④ COPPER GROUND CONDUCTOR. REMOVE INSULATION AT BUSHING, RUN THROUGH BUSHING LUG AND BOND TO RACEWAY SYSTEM. DO NOT SPLICE OR TAP.
- ⑤ CONTINUOUS COPPER GROUND CONDUCTOR FROM GROUND BUS THROUGH EACH BUSHING. DO NOT SPLICE OR TAP.




REF	SI	ENGLISH
A	26.3mm	1-1/16"
B	14.22mm	9/16"
C	28.58mm	1-1/8"
D	25.4MM	1"
E	457MM	1'-6"

GROUND BUS NOTES

1. GROUND BUS INSTALLATION SHALL BE IN ACCORDANCE WITH THIS DETAIL AND AS INDICATED ON THE DRAWINGS.



PLAN VIEW



ELEVATION

DETAIL - TYPICAL GROUND BUS PROVISIONS

NO SCALE

SHEET NOTES


1. ALL GROUNDING AND BONDING SHALL BE IN ACCORDANCE WITH THE NEC, NESC, IEEE, ANSI AND UL STANDARDS.
2. ALL DIMENSIONING INDICATED IN THESE DOCUMENTS ARE FOR REFERENCE AND COORDINATION PURPOSES ONLY. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL DIMENSIONS IN THE FIELD.
3. THE PURPOSE OF THE GROUNDING AND BONDING SYSTEM IS TO ESTABLISH ALL EQUIPMENT ENCLOSURES, NON-CURRENT CARRYING METALLIC PORTIONS OF THE ELECTRICAL DISTRIBUTION SYSTEM, METAL PIPING, METAL BUILDING FRAME, ETC., AT A ZERO POTENTIAL RELATIVE TO THE EARTH GROUND AND PROVIDE FOR A SAFE, LOW IMPEDANCE RETURN PATH FOR GROUND-FAULT CURRENT. THIS SHALL BE ACCOMPLISHED IN THE FOLLOWING MANNER:
  - a. PROVIDE A SOLIDLY GROUND SECONDARY SYSTEM.
  - b. INTER-CONNECT ALL GROUND BUSES AND POINTS IN THE SYSTEM WITH A COPPER GRD CONDUCTOR (BUS) SYSTEM.
  - c. ALL METALLIC RACEWAYS SHALL BE UL APPROVED AND MADE-UP TIGHT AT ALL COUPLINGS AND TERMINATIONS.
  - d. ALL GROUND CONDUCTORS IN CIRCUITS SHALL BE CONTAINED WITHIN THE SAME RACEWAY AS CURRENT CARRYING CONDUCTORS.
  - e. ALL SPLICES AND TERMINATIONS SHALL BE MADE TIGHT AND AS SUCH TO PROVIDE LOW IMPEDANCE AND SHALL HAVE THE SAME SHORT-TIME CURRENT-CARRYING CAPABILITY AS THE CONDUCTOR IT IS CONNECTED TO.
  - f. ALL GRD ELECTRODES OR BONDING CONDUCTORS INSTALLED ALONE WITHIN A RACEWAY SHALL UTILIZE GRC WITH GROUNDING BUSHINGS AT EACH END. THIS GROUND CONDUCTOR SHALL LOOP THROUGH THE BUSHING LUG PRIOR TO TERMINATION. INSTALL GROUNDING JUMPERS TO GROUND BUS AS APPLICABLE.
4. ALL GRD CONDUCTORS SHALL BE CONTINUOUS AND UNBROKEN FROM EACH LOCATION INDICATED. INSTALL IN GRC WITH GRD BUSH ON EACH END.
5. GRD ELECTRODE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH NEC.
6. MADE AND OTHER GRD SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH NEC.
7. ALL EQUIP NOT SUPPLIED WITH A GRD LUG SHALL BE PROVIDED WITH A LUG SIZED FOR THE GRD CONNECTION INDICATED AND PROVIDED WITH A TAP CONNECTION TO BOND EQUIP ENCLOSURE.
8. GROUNDING CONNECTIONS SHALL BE UL LISTED AND AS FOLLOWS:
  - BELOW GRADE: EXOTHERMIC WELDING
  - ABOVE GRADE: EXOTHERMIC WELDING, PRESSURE CONNECTORS
  - GRD RODS (ABOVE/BELOW GRADE): EXOTHERMIC WELDING
  - GRD BUS: PRESSURE CONNECTORS
  - EQUIP AND DEVICES: MECHANICAL LUG

DETAIL KEYED NOTES

- ① 9.52mm (3/8") X 38.1mm (1 1/2") SILICON-BRONZE MACHINE BOLT & SILICON-BRONZE WASHER
- ② 9.52mm (3/8") EXPANSION ANCHOR
- ③ 14.29mm (9/16") HOLE IN BAR
- ④ DRILLED DOUBLE CONNECTOR HOLES
- ⑤ FLAT, TWO-HOLE CU CABLE CONNECTOR #6 TO #2 (DOUBLE LUGS). #1 TO #4/0 (SINGLE LUGS ONLY)
- ⑥ 50.8mm (2") WIDE, 6.35mm (1/4") DEEP COPPER BUS BAR.
- ⑦ LENGTH AS REQUIRED BY NUMBER OF CONDUCTOR CONNECTIONS OR AS SPECIFICALLY INDICATED ON DRAWINGS. PROVIDE INTERMEDIATE WALL SUPPORTS AS REQUIRED.
- ⑧ TYP CU GRD CONDUCTOR CONNECTION
- ⑨ DESCRIPTION TAG. STATE SIZE OF CONDUCTOR AND TO WHAT IT IS CONNECTED TO.
- ⑩ TYP GRD CONNECTION FROM BELOW. SEE APPLICABLE DETAILS FOR SLAB PENETRATIONS.
- ⑪ TYP GRD CONNECTION FROM ABOVE. SEE APPLICABLE DETAILS FOR RMC INSTALLATIONS.
- ⑫ INSULATED NON-CONDUCTIVE STANDOFF(S) - 2,700 VOLT CLASS.

DETAIL NOTES

1. ALL GROUND ELECTRODE CONDUCTORS, SYSTEM BONDING CONDUCTORS, ETC., RUN SEPARATELY SHALL BE PROTECTED BY A CONDUIT SYSTEM.
2. ALL SYSTEM GROUNDING OR BONDING CONDUCTORS SHALL GENERALLY BE ENCLOSED BY A GRC CONDUIT. PROVIDE GROUND BUSHINGS ON EACH END AND BOND CONDUCTORS TO RACEWAY SYSTEM.
3. SYSTEM BONDING CONDUCTORS THAT PENETRATE CONCRETE SLABS SHALL BE ENCLOSED BY A PVC CONDUIT. PROVIDE BELL END FITTING ON EACH END AND SEAL. THOSE TERMINATING AT A STUB-UP SHALL BE FLUSH WITH FLOOR.



DETAIL - TYPICAL GROUND CONDUCTOR IN CONDUIT SYSTEM

NO SCALE



US Army Corps of Engineers

DATE	DESCRIPTION	MARK

DESIGNED BY: KLH	ISSUE DATE: NOVEMBER 2017	SOLICITATION NO.:	CONTRACT NO.:	PROJECT NUMBER:	FILE NAME:
CHECKED BY: KLH	DRAWN BY: EVL TEW				EBDEV7.dwg
SUBMITTED BY: KLH					
SIZE:	ANSI D				

US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA	BASKERVILLE DOWDY, INC. 1201 NORTH AVENUE DRIVE, SUITE 100 MOBILE, ALABAMA 36684-1000 205-833-1111 FAX: 205-833-1112 www.baskervilledowdy.com


PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT
TYPICAL GROUNDING DETAILS

SHEET ID

E-501

DETAIL NOTES

- FURNISH AND INSTALL PEDESTALS AT LOCATIONS INDICATED, MOUNTED ON CAST-IN-PLACE CONCRETE BASE.
- PROVIDE PVC CAST-IN-CONCRETE BOX BELOW EACH UNIT FOR FEEDER TERMINATION AND WIRING ACCESS.
  - * COORDINATE WITH WATER LINE STUB-UP




DETAIL - MARINE POWER PEDESTAL

NOT TO SCALE

DETAIL NOTES

- INSTALL CONDUIT FITTINGS FOR CONDUIT TURNS IN UTILITY TRENCH TYPE "LL" OR "LR" AS REQUIRED FOR CONDUCTOR PULLS.
- COVERS MUST BE ACCESSIBLE.




DETAIL - TYPICAL CONDULET FITTINGS

NOT TO SCALE

DETAIL NOTES

- INSTALL PVC CONDUIT CAST-IN-PLACE ON PIER TO EACH DEVICE.
- PROVIDE PVC CAST-IN-CONCRETE BOX BELOW EACH DEVICE FOR WIRING ACCESS.



DETAIL - PIER CONDUIT ROUTING

NOT TO SCALE

SHEET NOTES

- ALL CONDUIT SYSTEMS SHALL BE INSTALLED PER SPECIFICATIONS AND AS DETAILED TO SUPPORT PIER INFRASTRUCTURE.
- INSTALL CONDUIT SYSTEMS FROM PNL P THRU UTILITY TRENCH TO PIER. TURNS SHALL BE VIA CONDULET FITTINGS WITH GASKETED COVERS ON TOP FOR PULLING CONDUCTOR ACCESS.
  - * OFF-SET CONDUIT AS REQUIRED
  - * STAGGER FITTINGS AS REQUIRED
  - * SEE DETAIL C/E502
- INSTALL EXPANSION/DEFLECTION FITTINGS AT EACH PIER EXPANSION JOINT.
  - * SEE SHEET E-201

KEYED NOTES

- 3/4" CONDUIT FOR LIGHTING BOLLARDS
- 1" CONDUIT FOR MARINE POWER PEDESTALS



US Army Corps of Engineers®

MARK	DESCRIPTION	DATE

DESIGNED BY: KLH	ISSUE DATE: NOVEMBER 2017
DRAWN BY: EWH, TEW	SOLICITATION NO.:
CHECKED BY: KLH	CONTRACT NO.:
SUBMITTED BY: KLH	PROJECT NUMBER: MOT/TEV17
SIZE: ANSI D	FILE NAME: E502EV17.dwg

US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA


BASKERVILLE-DONOVAN, INC.
Innovative Infrastructure Solutions
1201 MONTGOMERY DRIVE, SUITE 600, MOBILE, AL 36688-1201
Pensacola - Panama City Beach - Tallahassee - Mobile - Shreveport - Tampa

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

TYPICAL ELECTRICAL
DETAILS

SHEET ID

E-502



SHEET NOTES

- 1. WIDTH OF INSTALLATION IS DEPENDENT ON MOUNTED EQUIPMENT PLUS 25%
  - * PANEL/TRANSFORMER
  - * RECEPTACLE
  - * LIGHTING CONTROLS
  - * LUMINAIRE
  - * GROUNDING PROVISIONS

KEYED NOTES

- 1. INSTALL GROUND TEST WELL.
- 2. 103mm (4") PLASTIC-COATED RIGID STEEL (GRS)
- 3. INSTALL EQUIPMENT AS NOTED IN SINGLE LINE DIAGRAM. ADD ADDITIONAL STRUT AND/OR ADJUST ACCORDINGLY.
- 4. UTILITY TRENCH GROUND CONDUCTOR
  - * #1/0 CU GRD
  - * SEE PIER GROUNDING PLAN

US Army Corps of Engineers

ISSUE DATE	NOVEMBER 2017	SOLICITATION NO.	CONTRACT NO.	PROJECT NUMBER	FILE NAME	MARK	DESCRIPTION	DATE
DESIGNED BY:	KLH	DRAWN BY:	EWJ, TEW	CHECKED BY:	KLH	SUBMITTED BY:	KLH	SIZE: A3/D
US ARMY CORPS OF ENGINEERS MOBILE DISTRICT MOBILE, ALABAMA								
BASKERVILLE-DONOVAN, INC. Innovative Infrastructure Solutions 1301 MONTAUBAN DRIVE, SUITE 600, MOBILE, AL 36688-0311 Permitting - Planning Civil Design - Telecommunications - Marine - Research County - Tampa								

PONCE, PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

TYPICAL BACKBOARD STRUCTURE

SHEET ID
E-503

TRANSFORMER SCHEDULE						
MARK	KVA	PRI VOLTAGE	SECONDARY VOLTAGE	Z	MTG	NOTES
TX-P1	15	240V, 1PH	480V, 1PH	—	WALL	STEP-UP
TX-P2	15	480V, 1PH	120/240V, 1PH	—	WALL	STEP-DOWN



TRANSFORMER INSTALLATION NOTES

1. SIZE ALL SUPPORTS, ANCHOR SYSTEMS, BOLTS, ETC., AS REQUIRED FOR A SECURE INSTALLATION IN ACCORDANCE WITH THE SPECIFICATIONS.
2. EACH TRANSFORMER SHALL BE PROVIDED WITH VIBRATION ISOLATION. PROVIDE ADDITIONAL SPECIAL VIBRATION OR ISOLATION PADS (FLEXIBLE MOUNTS OR VIBRATION DAMPENERS WHEN INSTALLED TO A WALL)
3. SEE TRANSFORMER SCHEDULE FOR MOUNTING REQUIREMENTS.
4. ALL WALL UNITS SHALL BE PROVIDED WITH ACCESSORIES FROM THE MANUFACTURER SPECIFICALLY FOR THAT PURPOSE.

IN EACH PHASE CONNECT TO TAPS	
PRIMARY VOLTS	2-2.5% FCAN 4-2.5% FCBN
504	1-8
492	1-7
480	2-7
460	2-6

TAP SETTING NOTE:

THE CONTRACTOR SHALL SET TAPS AT THE PROPER SETTING TO COMPENSATE FOR VOLTAGE VARIATIONS DUE TO LOAD CONDITIONS.



SHEET NOTES

1. DRY-TYPE TRANSFORMERS SHALL CONSIST OF BUT NOT BE LIMITED TO THE FOLLOWING:
  - a. ENCAPSULATED & SEALED ENCLOSURE
* NEMA 4X
  - b. PRIMARY SECTION
  - c. SECONDARY SECTION
  - d. OVERCURRENT PROTECTION
2. INSTALLATION SHALL COMPLY WITH THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AND THE NATIONAL ELECTRICAL SAFETY CODE (NESC).
3. ALL CONDUCTIVE PARTS OF EQUIPMENT, ENCLOSURES, FRAMES, ETC., SHALL BE GROUNDED.
4. ALL CLEARANCES SHALL BE MAINTAINED PER NESC AND NEC. ALL PARTS, DEVICES, EQUIPMENT, ETC. WHICH REQUIRE MAINTENANCE, ADJUSTMENT, OPERATION OR EXAMINATION DURING NORMAL NETWORK OPERATION SHALL BE ARRANGED SO AS TO BE ACCESSIBLE BY THE PROVISION OF ADEQUATE WORKING SPACES, WORKING FACILITIES AND CLEARANCES. UNLESS NOTED OTHERWISE ALL CLEARANCES ARE MEASURED FROM SURFACE TO SURFACE.
5. ALL DIMENSIONS INDICATED IN THESE DOCUMENTS ARE FOR REFERENCE AND COORDINATION PURPOSES ONLY. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL DIMENSIONS IN THE FIELD.
6. TRANSFORMERS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND APPLICABLE DETAILS, ACCESSIBLE WITH MECHANICAL PROTECTION, NEMA 4X SEALED ENCLOSURES AND WITHIN A SPACE TO PROVIDE VENTILATION TO DISPOSE OF THE TRANSFORMER FULL LOAD LOSSES. EACH TRANSFORMER SHALL CONTAIN A NAMEPLATE IN ACCORDANCE WITH NEC AND THE CONTRACTOR SHALL INSURE THAT ALL SPECIAL PRECAUTIONS ARE MET SUCH AS PROPER CLEARANCES FOR VENTILATION, OVERCURRENT PROTECTION, ETC.

KEYED NOTES

- ① LIQUID-TIGHT FLEXIBLE METAL CONDUIT AND FITTINGS PRIMARY CONDUIT SYSTEM
- ② LIQUID-TIGHT FLEXIBLE METAL CONDUIT AND FITTINGS SECONDARY CONDUIT SYSTEM
- ③ GROUNDING BUSHING

US Army Corps
of Engineers ®[illegible]

BASKERVILLE DONOVAN, INC. 1201 MCCLURE DRIVE, SUITE 600, BIRMINGHAM, AL 35202 (205) 366-0111 ENGINEERING BUSINESS LICENSE #00000000		DRAWN BY: EWH, TEW CHECKED BY: KJH SUBMITTED BY: KJH	SOLICITATION NO.: NOVEMBER 2017 CONTRACT NO.: PROJECT NUMBER: M017EV17	FILE NAME: ES04EV17.dwg ANS I D

PONCE, PUERTO RICO
 PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT
 DRY TYPE TRANSFORMER
 DETAILS AND SCHEDULES

SHEET ID
E-504

LUMINAIRE SCHEDULE

LUMINAIRE MARK	USACE STANDARD DETAILS		LUMINAIRE					MTG	LUMINAIRE VOLTAGE	LUMINAIRE CRITERIA					NOTE NO
	TYPE	LUMEN OUTPUT	WATTAGE	COLOR TEMP	NUMBER OF DRIVERS	DRIVE CURRENT	NUMBER OF LED BOARDS			ZONAL CAVITY METHOD ASSUME RCR = 1			SPACING TO MTG HGT RATIO		
										EFFECTIVE REFLECTANCE				CU	
MARK	TYPE	OUTPUT	WATT	TEMP	TYPE	CURRENT	BOARDS	MTG	VOLT	CLG	WALL	FLOOR	CU		SPACING
BD	XL-12	350	16W	LWA	1	450mA	--	CB	120	--	--	--	--	--	3,5,6
WP	XL-17	1,290	14W	5,000	1	--	--	W	120	--	--	--	--	--	3

LUMINAIRE SCHEDULE NOTES

1. THE CONTRACTOR SHALL SUBMIT, FURNISH AND INSTALL A LUMINAIRE WITH SIMILAR LUMINAIRE CRITERIA LISTED IN THE SCHEDULE. THE DESIGN AND LAYOUT PRESENTED IS BASED UPON THE INFORMATION CONTAINED IN THE COLUMNS UNDER "LUMINAIRE CRITERIA" AND ANY DEVIATION MAY REQUIRE THE CONTRACTOR TO FURNISH ADDITIONAL LUMINAIRES BASED ON NEW LIGHTING CALCULATIONS TO MEET THE DESIGN INTENT.

2. UNIT SHALL CONTAIN UL DAMP LOCATION LABEL.

3. UNIT SHALL CONTAIN UL WET LOCATION LABEL.

4. UNIT SHALL BE CONNECTED AHEAD OF LOCAL SWITCHING.

5. LUMINAIRE SHALL BE EQUIPPED WITH LIMITED WAVELENGTH AMBER LEDs.

6. LUMINAIRE SHALL HAVE ASYMMETRIC DISTRIBUTION PATTERN.

LUMINAIRE SCHEDULE AND LAMP/BALLAST CHART – KEY LEGEND & TERMINOLOGY

LAMP TYPES		LAMP DESIGNATION		LUMINAIRE MOUNTING		IES LIGHTING TERMS	
LED	LIGHT EMITTING DIODE	A	A – LAMP	C	CEILING	CCT	COLOR CORRECTED TEMPERATURE
LWA	LIMITED WAVELENGTH AMBER	FL	FLOOD	CB	CONCRETE BASE	CRI	COLOR RENDERING INDEX
		MFL	MEDIUM FLOOD	CH	CHAIN HANG	CU	COEFFICIENT OF UTILIZATION
		NFL	NARROW FLOOD	D	DESK	CDC	CANDLE POWER DISTRIBUTION CURVE
		WFL	WIDE FLOOD	F	FLOOR	CBCP	CENTER BEAM CANDLE POWER
		HO	HIGH OUTPUT	G	GRADE	FC	FOOTCANDLES
		IF	INSIDE FROSTED	P	PENDANT	K	DEGREES KELVIN
		MR	MIRRORED REFLECTOR	PT	POST TOP	LUX	METRIC FOOTCANDLE (FC X 10.8)
		PAR	PARABOLIC ALUMINUM REFLECTOR	R	RECESS	RCR	ROOM CAVITY RATIO
		SP	SPOT	RL	RECESS LAY – IN	LUMENS	MEASURED OUTPUT OF LAMP, LUMINAIRE, OR BOTH
		VHO	VERY HIGH OUTPUT	RF	RECESS FLANGE		LUMINAIRE COMPLETE LIGHTING UNIT, INCLUDING LAMP, REFLECTOR, AND HOUSING
		W	WATT	RW	RECESS WALL		
				S	SURFACE		
				SR	SEMI – RECESS		
				T	TRACK		
				U	UNIVERSAL		
				UC	UNDERCABINET		
				W	WALL		

LUMINAIRE NOTES

1. LUMINAIRE AND LUMINAIRE INSTALLATION SHALL BE IN ACCORDANCE WITH NFPA 70, ARTICLE 410. ALL LUMINAIRES SHALL BE UL LISTED AND INSTALLED IN ACCORDANCE WITH THE UL LISTING "FIXTURE MARKING GUIDE" AND SUPPORTED BY MEANS DESIGNED FOR THAT LISTED INSTALLATION. ALL CLEARANCES REQUIRED BY CODE SHALL BE MAINTAINED. LUMINAIRES INSTALLED IN UNUSUAL CONDITIONS SUCH AS DAMP, WET, ETC., LOCATIONS SHALL BE MARKED AND LABELED FOR THE PURPOSE.

2. EACH LUMINAIRE SHALL BE FURNISHED COMPLETE WITH THE PROPER DRIVER, SURGE SUPPRESSION, DIMMING CONTROLS, WIRING COMPONENTS, SUPPORTING FRAMES AND/OR DEVICES, ETC., FOR A COMPLETE INSTALLATION SUITABLE WITH THE AMBIENT CONDITIONS ENCOUNTERED. ALL DEVICES, COMPONENTS, FITTINGS, SUPPORTS, ETC., SHALL BE COORDINATED TO PROVIDE A COMPLETE UL LISTED INSTALLATION.

3. EACH LUMINAIRE SHALL BE FURNISHED WITH GROUNDING PROVISIONS AND BE GROUNDED TO THE GROUNDING PROVISIONS OF THE WIRING SYSTEM.

4. LUMINAIRES SHALL NOT BE INSTALLED IN CONTACT WITH COMBUSTIBLE MATERIALS. ADEQUATE SPACE FOR AIR CIRCULATION AND CODE COMPLIANCE SHALL BE PROVIDED AS A MINIMUM. FURNISH SPACERS, WASHERS, SUPPORT DEVICES, ETC., AS REQUIRED TO MAINTAIN PROPER CLEARANCES. LUMINAIRES SHALL BE CONSTRUCTED, INSTALLED AND EQUIPPED SUCH THAT ADJACENT MATERIAL WILL NOT BE SUBJECTED TO TEMPERATURES IN EXCESS OF 90°C (194°F).

5. OUTLET BOXES, CONDUCTORS, SPLICES AND TERMINATIONS SHALL BE ACCESSIBLE. ONLY CONDUCTORS RATED FOR THE ENVIRONMENTAL CONDITIONS, CURRENT, VOLTAGE AND TEMPERATURES ENCOUNTERED SHALL BE USED.

6. ALL ADJUSTABLE LUMINAIRES SHALL BE ADJUSTED FOR FINAL APPROVAL DURING NON-DAYLIGHT HOURS.

7. LED MODULE/DRIVER CONTROL COMBINATIONS SHALL BE COMPATIBLE IN ACCORDANCE WITH MANUFACTURER'S TESTING DATA AND RECOMMENDATIONS.

* DRIVERS SHALL MEET 47 CFR, PART 18, FOR RF EMISSIONS.

* DRIVERS SHALL NOT EXCEED 20% TOTAL HARMONIC DISTORTION (THD)

* DRIVERS SHALL BE COMPATIBLE WITH DIMMING AND SWITCHING SCHEMES.

8. LED LUMINAIRE'S LUMEN MAINTENANCE SHALL MEET OR EXCEED THE LATEST VERSION OF IES LM-80 TESTING STANDARDS. LUMINAIRE PHOTOMETRICS SHALL COMPLY WITH THE LATEST VERSION OF IESNA LM-79 TESTING CRITERIA.

9. ALL LUMINAIRES SHALL COMPLY WITH MINIMUM ENERGY EFFICIENCY REQUIREMENTS OF APPLICABLE CODES.

10. LED MODULES/DRIVERS SHALL BE ACCESSIBLE AND UPGRADABLE.

11. LUMINAIRES SHALL HAVE INTEGRAL SURGE SUPPRESSION WHEN APPLICABLE.

LED SPECIFICATIONS

LED LUMINAIRES SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND RATINGS. LUMINAIRE MANUFACTURER SHALL HAVE BEEN ENGAGED IN MANUFACTURING LUMINAIRES AND ACCESSORIES FOR 10 YEARS PRIOR TO BID OPENING. LUMINAIRES SHALL HAVE BEEN IN SATISFACTORY COMMERCIAL OR INDUSTRIAL USE FOR TWO YEARS PRIOR TO BID OPENING. ALL LUMINAIRES SHALL MEET ANY NATIONAL OR LOCAL REGULATIONS.

TYPE	COLOR TEMP	LUMEN OUTPUT	CRI	LUMENS PER WATT	LUMEN MAINTENANCE PERCENTAGE	LUMEN MAINTENANCE HOUR INTERVAL
BOLLARDS	LWA	350	70	22	95	100,000
EXTERIOR WALL PACK	5,000K	1,300	80	92	75	100,000

LUMINAIRE REQUIREMENTS:

1. HOUSING – EXTRUDED DIE-CAST ALUMINUM SHAFT, REFLECTOR & TOP CAP. ALL EXPOSED HARDWARE SHALL BE STAINLESS STEEL.

2. FINISH – MULTI-STAGE PRE-TREATMENT, FINISHED WITH BAKED-ON POLYESTER POWDER COAT. FINISH SHALL PASS 2500 HOUR SALT SPRAY TEST PER ASTM B117.

3. DRIVER – TYPE C – CLASS 1, CONSTANT CURRENT, ELECTRONIC DRIVER FOR HIGH EFFICIENCY LED LIGHT SOURCE. ELECTRICAL COMPONENTS SHALL BE SERVICEABLE AND UPGRADABLE. ALUMINUM HEAT SINKS SHALL MAXIMIZE HEAT DISSIPATION.

4. OPTICAL ASSEMBLY – TYPE C – DIRECTIONAL FULL CUTOFF LED ASSEMBLIES FOR MAXIMUM BEAM ANGLE PROJECTION THROUGH OPENINGS IN LUMINAIRE BODY. PROVIDE ASYMMETRIC DISTRIBUTION AS INDICATED WITH 0% UPLIGHT.

5. LIGHT SOURCE – LED SOURCE. AMBER LIMITED WAVE LENGTH.

6. CERTIFICATION – UL AND/OR ETL LISTED FOR WET LOCATION AND RoHS COMPLIANT.

7. OPTIONS – CLEAR LENS, HOUSE SIDE SHIELD FOR 180 DEGREE COVERAGE.

LUMINAIRE REQUIREMENTS:

1. HOUSING – HEAVY-DUTY DIE-CAST ALUMINUM WITH INTEGRAL PASSIVE COOLING HEAT SINKS. HEAT SINK SHALL BE INCORPORATED DIRECTLY INTO HOUSING OR DRIVER COMPARTMENT TO ENSURE MAXIMUM HEAT TRANSFER AND DISSIPATION. HOUSING SHALL BE SEALED AGAINST MOISTURE AND ENVIRONMENTAL CONTAMINANTS.

2. FINISH – MULTI-STAGE PRE-TREATMENT, FINISHED WITH TEXTURED BAKED-ON POLYESTER POWDER COAT. FINISH SHALL PASS 2500 HOUR SALT SPRAY TEST PER ASTM B117. STANDARD FINISH IS DARK BRONZE.

3. POWER SUPPLY/LED DRIVER – CLASS 1 DRIVER SHALL OPERATE AT 120 VOLTS, 60 HZ; ELECTRONIC DRIVER SHALL HAVE A POWER FACTOR GREATER THAN 0.9 AND THD LESS THAN 20% AT FULL LOAD.

4. LED OPTICAL ASSEMBLY – HIGH PERFORMANCE LEDS BEHIND CLEAR GLASS LENS PRODUCING NEMA TYPE III DISTRIBUTION. MINIMUM COLOR RENDERING INDEX (CRI) SHALL BE 70 FOR CORRELATED COLOR TEMPERATURE (CCT) OF 5000 DEGREES K. FULL CUTOFF WITH ZERO UPLIGHT.

5. CERTIFICATION – UL AND/OR ETL LISTED WET LOCATIONS AS INDICATED, AND RoHS COMPLIANT.

LED BOLLARD

NO SCALE

TYPE 'BD'

LED WALL LUMINAIRE

NO SCALE

TYPE 'WP'

US ARMY CORPS of Engineers®

ISSUE DATE: NOVEMBER 2017

SOLICITATION NO.:

CONTRACT NO.:

PROJECT NUMBER: M017EV17

FILE NAME: E601EV17.dwg

DESIGNED BY: K/LH

DRAWN BY: EWH, TEW

CHECKED BY: K/LH

SUBMITTED BY: K/LH


SIZE: ANSI D

US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA
BASKERVILLE-PONDYAN, INC.
Innovative Infrastructure Solutions
1225 MONTGOMERY DRIVE, SUITE 100, MOBILE, AL 36688-1541
Ponchartraine • Panama City Beach • Tallahassee • Mobile • Brewster County • Tampa


POINCE, PUERTO RICO
POINCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

LUMINAIRE SCHEDULE & NOTES


SHEET ID
E-601



A
E801
EXTERIOR POLE MOUNT PTZ CAMERA
NOT TO SCALE



B
E-801
DETAIL - POLE BASE DETAIL
NOT TO SCALE



C
TYPICAL CLOSED CIRCUIT TELEVISION (CCTV) SYSTEM RISER DIAGRAM
NOT TO SCALE

RISER DIAGRAM KEYED NOTES

- ① NEW CAMERA LOCATION
* PAN/TILT/ZOOM (PTZ)
* NIGHT VISION TYPE

SECURITY SURVEILLANCE TV SYSTEM EQUIP. LEGEND	
SYMBOL	DESCRIPTION
	EXISTING CHANNEL NETWORK VIDEO RECORDER
	EXISTING CONTROLLER
	EXTERIOR PAN/TILT/ZOOM (PTZ) CAMERA
	RG 59/U COAXIAL CABLE IN CONDUIT

SHEET NOTES

- ADD A NEW 8-CHANNEL VIDEO RECORDER TO THE EXISTING CCTV HEAD-END EQUIPMENT.
* MUST BE COMPATIBLE WITH EXISTING UNIT.
* PROVIDE ALL INTER-CONNECTIONS
- EXTEND THE EXISTING SYSTEM TO INCLUDE ONE ADDITIONAL CAMERA LOCATION:

INSTALLATION NOTES

- IN GENERAL EACH CONCRETE POLE SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S REQUIREMENTS AND/OR RECOMMENDATIONS. DIMENSIONS ARE TYPICAL ONLY AND ACTUAL DEPTH SHALL BE DEPENDENT UPON SOIL CONDITIONS ENCOUNTERED.
- EXCAVATION SHALL BE AS NECESSARY TO ALLOW FOR PROPER POLE INSTALLATION, UTILITY AND GROUNDING SYSTEM TRENCHING, BACKFILLING REQUIREMENTS, ETC. ALL SURFACES SHALL BE CUT, PATCHED AND REPAIRED TO THEIR ORIGINAL CONDITION. ALL DAMAGED UTILITY SYSTEMS, UNDERGROUND CIRCUITS, DEVICES, STRUCTURES, ETC., SHALL BE REPAIRED AND PLACED BACK INTO OPERATION.
- ACTUAL DEPTH TO BE PER POLE MANUFACTURER'S RECOMMENDATIONS.
- INSTALL A CONTINUOUS COPPER GROUND CONDUCTOR FROM TOP OF POLE TO GROUND ROD CONNECTION.
• SUPPORT TO POLE 152mm O.C. WHEN EXPOSED
• SUPPORT TO POLE 610mm O.C. OTHERWISE
• DO NOT BEND GREATER THAN 45 DEGREES.
- WHERE EXPOSED, GROUND CONDUCTOR SHALL BE LOCATED ON SAME SIDE AS NEUTRAL CONDUCTOR AND IN QUADRANT OPPOSITE CLIMBING SPACE.
- BOND ALL NON-CURRENT CARRYING METAL PARTS OF EQUIPMENT, ENCLOSURES, FRAMES, DEVICE SUPPORTS, BRACKETS, CONDUCTOR ASSEMBLIES, ETC.

US Army Corps of Engineers®

ISSUE DATE:	NOVEMBER 2017	SOLICITATION NO.:	CONTRACT NO.:	PROJECT NUMBER:	FILE NAME:
DESIGNED BY:	KLH	DRAWN BY:	EMH, TEW	CHECKED BY:	KLH
SUBMITTED BY:	KLH	SIZE:	ANSI D	FILE NAME:	E801EVT7.dwg

US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA

BASKERVILLE-DONOVAN, INC.
Innovative Infrastructure Solutions
1201 MONTICLOAK DRIVE, SUITE 600, MOBILE, AL 36689 (251) 388-3311
Pensacola • Panama City Beach • Tallahassee • Mobile • Grand County • Tampa

PONCE PUERTO RICO
PONCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT

SECURITY SYSTEMS REQUIREMENTS

SHEET ID
E-801

FEEDER SCHEDULE

MARK	CONDUCTORS	CONDUIT		REMARKS
		SI	ENGLISH	
A	2#4 & 1#8 GRD	27mm	1"	
B	2#6 & 1#8 GRD	27mm	1"	
C	2#12 & 1#12 GRD	21mm	3/4"	
D	2#10 & 1#10 GRD	21mm	3/4"	
E	3#4 & 1#8 GRD	21mm	3/4"	FLEX
F				
G				
H				
I				
J				
K				

NOTES:
1. ALL CONDUCTOR SIZES ARE INDICATED IN AMERICAN WIRE GAUGE (AWG) OR 'KCMIL' UNLESS NOTED OTHERWISE.
2. UNLESS NOTED OTHERWISE LOW VOLTAGE CONDUCTORS SHALL BE RATED AT 600 VOLTS BASED UPON AN AMBIENT TEMPERATURE OF 30 DEGREES C AND AS FOLLOWS:
• COPPER
• INSULATED (THW OR THHN/THWN TYPE)
• TEMPERATURE RATING - 75 DEGREES C
3. SEE "CONDUCTOR SCHEDULE & PROPERTIES DESIGNATIONS"

FUSE SCHEDULE - LOW VOLTAGE

DES	DESCRIPTION	REMARKS	UL AIC RATING
MCF	MISCELLANEOUS CARTRIDGE FUSES	UTILIZE IN CONTROL AND/OR ELECTRONIC CIRCUITS ONLY.	NOT RATED
H	CLASS H	ANSI/UL 198B 600 AMPERES & LESS	10,000 AMPERES
HTD	CLASS H TIME DELAY	ANSI/UL 198B MIN DELAY OF 10S @ 50% OF RATING 600 AMPERES & LESS	10,000 AMPERES
RK1	CLASS RK1 CURRENT LIMITING	ANSI/UL 198E 600 AMPERES & LESS	200,000 AMPERES
RK5	CLASS RK5 CURRENT LIMITING DUAL-ELEMENT TIME DELAY	ANSI/UL 198E 600 AMPERES & LESS	200,000 AMPERES
L	CLASS L CURRENT LIMITING	ANSI/UL 198C 601 TO 6000 AMPERES	200,000 AMPERES
T	CLASS T CURRENT LIMITING (REDUCED SIZE)	ANSI/UL 198H 600V - 800 AMPERES & LESS 250V - 1200 AMPERES & LESS	10,000 AMPERES

NOTES:
1. FUSES SHALL BE IN ACCORDANCE WITH ANSI C97.1 AND THE ANSI/UL 198 SERIES. THE NONRENEWABLE TYPE, AND SHALL BE APPLIED AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATION AND CONTRACT DOCUMENTS.

DIAGRAM SYMBOLS

DISCONNECT SWITCH - NONFUSIBLE
DISCONNECT - FUSIBLE
MOTOR CONTROLLER
COMBINATION CONTROLLER/CIRCUIT BREAKER
COMBINATION CONTROLLER/FUSED DISCONNECT SWITCH
CIRCUIT BREAKER (GFCI TYPE)
CIRCUIT BREAKER
NONFUSIBLE SWITCH
FUSIBLE SWITCH
TRANSFER SWITCH
CONTACTS - NORMALLY OPEN
CONTACTS - NORMALLY CLOSED
THERMAL ELEMENT
FUSIBLE ELEMENT
COIL
FUSE
TRANSFORMER WINDINGS
INSTRUMENT TRANSFORMER
CURRENT TRANSFORMER
ALTERNATING CURRENT POWER SOURCE
DIRECT CURRENT POWER SOURCE
BATTERY
WEATHERHEAD
SPLICE
DRAWOUT CONNECTION
BUILDING PENETRATION/SEAL

SINGLE LINE DIAGRAM NOTES

1. THE PURPOSE OF THE DIAGRAM IS TO DEMONSTRATE THE POWER SYSTEM SERVICE REQUIREMENTS, BUS CAPACITIES, FEEDER REQUIREMENTS, LEVELS OF PROTECTION, ETC., IN ORDER TO PROVIDE A COORDINATED AND PROTECTED POWER DISTRIBUTION SYSTEM.

2. AMPERE INTERRUPTING CAPACITY OR SHORT CIRCUIT CURRENT RATINGS ARE INDICATED AT VARIOUS BUSES IN THE SYSTEM AND THE CONTRACTOR SHALL COORDINATE, FURNISH AND INSTALL THE PROPER EQUIPMENT, DEVICES, TERMINATIONS AND MATERIAL AT THOSE LOCATIONS CAPABLE OF INTERRUPTING AND/OR WITHSTANDING THESE CURRENTS WITHOUT DAMAGE IN ACCORDANCE WITH UL AND THE NEC.

3. ALL OVERCURRENT PROTECTIVE DEVICES FOR THIS PROJECT SHALL BE CURRENT SENSING DEVICES AND SHALL PROTECT ALL BUSES, CONDUCTORS, EQUIPMENT, DEVICES, MOTORS, APPLIANCES, TRANSFORMERS AND SYSTEMS INDICATED. THE FOLLOWING TYPES OF PROTECTION SHALL BE PROVIDED:
• OVERCURRENT
• SHORT CIRCUIT
• GROUND-FAULT
• OVERLOAD
THE FOLLOWING TYPES OF DEVICES ARE TO BE USED AND COORDINATED FOR THIS PROJECT:
• CIRCUIT BREAKERS
• FUSES
• GROUND-FAULT SENSING DEVICES

4. APPLICATION, INSTALLATION AND CONNECTION OF ALL DEVICES SHALL BE IN ACCORDANCE WITH THE NEC, MANUFACTURER'S RECOMMENDATIONS AND CONTRACT DOCUMENTS.

5. ALL EQUIPMENT LOADS AND PROTECTION ARE TYPICAL AND BASED UPON DESIGN CALCULATIONS FOR BIDDING PURPOSES. THE CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE AND VERIFY WITH ALL DIVISIONS THE ACTUAL NAMEPLATE DATA OF ALL EQUIPMENT AND DEVICES SUPPLIED ON THIS PROJECT. BASE BID SHALL INCLUDE PROVIDING THE PROPER PROTECTIVE DEVICES FOR ALL COMPONENTS OF THE ELECTRICAL SYSTEM IN ACCORDANCE WITH NOTE 3 ABOVE AND AS PER EQUIPMENT MANUFACTURER'S NAMEPLATE DATA OR INSTRUCTIONS. THE CONTRACT DRAWINGS MAY NOT SIZE THE ACTUAL FUSE SIZE FOR CERTAIN SYSTEMS AND THE CONTRACTOR WILL BE RESPONSIBLE TO SIZE IN ACCORDANCE WITH NAMEPLATE DATA AND FURNISH THIS INFORMATION WITH THE AS-BUILT DRAWINGS.

6. CIRCUIT BREAKERS SHALL BE INSTALLED AS INDICATED RATED FOR THE PROPER VOLTAGE POTENTIAL, CURRENT, FREQUENCY, AND THE INTERRUPTING RATING INDICATED. CIRCUIT BREAKERS SHALL BE INSTALLED IN UL LISTED ENCLOSURES WITHIN THE ENVIRONMENTAL LIMITATION LISTED OF THE UNIT, SUCH AS AMBIENT TEMPERATURE, HUMIDITY, CLEAN & FREE FROM CONTAMINANTS. CIRCUIT BREAKERS SHALL PROVIDE SIMULTANEOUS DISCONNECTION OF ALL PHASE CONDUCTORS DURING TRIPPING. ALL LOW VOLTAGE CIRCUIT BREAKERS WITHIN THE SYSTEM SHALL BE OF THE SAME MANUFACTURER SO THAT COORDINATION UP AND DOWN STREAM CAN BE FACILITATED.

7. FUSES SHALL BE INSTALLED AS INDICATED, RATED FOR THE PROPER VOLTAGE POTENTIAL, CURRENT, FREQUENCY, MAXIMUM PEAK LET THROUGH, MAXIMUM CLEARING THERMAL ENERGY (I²T), AND THE INTERRUPTING RATING INDICATED. FUSES SHALL BE INSTALLED IN UL LISTED ENCLOSURES WITHIN THE ENVIRONMENTAL LIMITATION LISTING OF THE UNITS, SUCH AS AMBIENT TEMPERATURE, HUMIDITY, CLEAN & FREE FROM CONTAMINANTS. ALL FUSES WITHIN THE SYSTEM SHALL BE OF THE SAME MANUFACTURER SO THAT COORDINATION UP AND DOWN STREAM CAN BE FACILITATED. WHEN APPLYING AND INSTALLING PROTECTIVE DEVICES THE CONTRACTOR SHALL TAKE INTO CONSIDERATION THE FOLLOWING:
• STEADY STATE CONTINUOUS CURRENT
• IN-RUSH CURRENT FROM MOTOR STARTING
• IN-RUSH CURRENT FROM TRANSFORMER MAGNETIZING UNDER LOAD
• SHORT CIRCUIT WITHSTAND RATINGS-NEC 110-10 AND 240-1
• INTERRUPTING RATINGS-NEC 110-9 AND 230-65
• CURRENT LIMITING LET THROUGH CURRENTS-NEC 240-11

8. THE CONTRACTOR IS TOTALLY RESPONSIBLE FOR THE INSTALLATION, MARKING AND CONNECTING OF ALL POWER CONDUCTORS FOR THE PROPER PHASE SEQUENCE AND BALANCED LOADING.

US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA

DESIGNED BY: KLH
DRAWN BY: EWH, TEW
CHECKED BY: KLH
SUBMITTED BY: KLH
SIZE: ANSI D

ISSUE DATE: NOVEMBER 2017
SOLICITATION NO.:
CONTRACT NO.:
PROJECT NUMBER: M07EVI7
FILE NAME: ESD0EVI7.dwg

US ARMY CORPS OF ENGINEERS
MOBILE DISTRICT
MOBILE, ALABAMA
BASKERVILLE-PONDYAN, INC.
1201 LOCKLAND DRIVE, SUITE 100, MOBILE, AL 36688-0111
Ponchartraine, Louisiana
Ponchartraine, Louisiana

POINCE, PUERTO RICO
POINCE MARINE UNIT - PIER & BOAT RAMP REPLACEMENT
SINGLE LINE DIAGRAM
NOTES AND SCHEDULES

SHEET ID
E-900

